St. LouisRegional
EAST ALTON, ILLINOIS

SUMMARY OF QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	as Built Quantities	
AR106511	TYPE A AREA LGHT POLE W/1 FIXTURE	EA.	4		
AR108658	3/C #8 600V UG CABLE IN UD	L.F.	804		
AR110014	4" DIRECTIONAL BORE	L.F.	48		
AR110502	2WAY CONCRETE ENCASED DUCT	L.F.	28		
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1		
AR150530	TRAFFIC MAINTENANCE	LS.	1		
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	2,675		
AR156510	SILT FENCE	L.F.	640		
AR156511	DITCH CHECK	EA.	9		
AR156520	INLET PROTECTION	EA.	3		
AR156521	HEADWALL PROTECTION	EA.	6		
AR162508	CLASS E FENCE 8'	L.F.	303		
AR162605	CLASS E GATE - 5'	EA.	1		
AR162724	ELECTRIC GATE - 24'	EA.	1		
AR162900	REMOVE CLASS E FENCE	L.F.	360		
AR201610	BITUMINOUS BASE COURSE	TON	621		
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	933		
AR401610	BITUMINOUS SURFACE COURSE	TON	294		
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	35		
AR501604	4" PCC SIDEWALK	S.F.	422		
AR501910	REMOVE & REPLACE PCC PAVEMENT	S.Y.	81		
AR602510	BITUMINOUS PRIME COAT	GAL.	630		
AR603510	BITUMINOUS TACK COAT	GAL.	270		
AR620520	PAVEMENT MARKING — WATERBORNE	S.F.	643		
AR701515	15" RCP, CLASS IV	L.F.	412.5		
AR701518	18" RCP. CLASS IV	L.F.	53		
AR701900	REMOVE PIPE	L.F.	480		
AR705546	6" NON PERFORATED UNDERDRAIN	L.F.	50		
AR705548	8" NON PERFORATED UNDERDRAIN	L.F.	190		
AR751411	INLET-TYPE A	EA.	3		
AR751540	MANHOLE 4'	EA.	1		
AR751900	REMOVE INLET	EA.	1		
AR752412	PRECAST REINFORCED CONC. FES 12"	EA.	6		
AR752415	PRECAST REINFORCED CONC. FES 15"	EA.	1		
AR752418	PRECAST REINFORCED CONC. FES 18"	EA.	2		
AR754210	CONCRETE CURB	L.F.	79		
AR760506	6" DUCTILE IRON WATER MAIN	L.F.	12		
AR760508	8" DUCTILE IRON WATER MAIN	L.F.	447		
AR760716	16" STEEL CASTING	L.F.	60		
AR760800	FIRE HYDRANT	EA.	1		
AR760861	8"X8" TAPPING VALVE & SLEEVE	EA.	1		
AR760965	RELOCATE, FIRE HYDRANT	EA.	1		
AR901510	SEEDING	AC.	1.8		
AR908510	MULCHING	AC.	1.8		
AR910200	ROADWAY SIGN	EA.	3		
AR910410	PARKING BLOCK	EA.	8		

INDEX TO SHEETS		
SHEET NO.	DESCRIPTION	REGIONAL AIRPORT
1	COVER SHEET	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
2	SUMMARY OF QUANTITIES, INDEX TO SHEETS	<u>~</u>
3	PROPOSED SAFETY PLAN	
4	PROPOSED GEOMETRIC PLAN	ᅱ
5	PROPOSED TYPICAL SECTION	≥
6	PROPOSED PAVEMENT REMOVAL DETAILS	ō
7	PROPOSED CONSTRUCTION PLAN	
8	EXISTING UTILITY PLAN	й
9	PROPOSED PLAN AND PROFILE	
10	PROPOSED DRAINAGE PLAN AND PROFILE	Fours
11	PROPOSED DRAINAGE DETAILS	5
12	PROPOSED STAKING PLAN	O
13	PROPOSED WATERLINE PLAN AND PROFILE	
14	PROPOSED WATERLINE DETAILS	rs rs
15	PROPOSED ROADWAY LIGHTING PLAN AND ELECTRICAL DUCT DETAILS	Ø
16	ONE-LINE FOR GATE OPERATOR AND ROADWAY	
17	ELECTRIC GATE DETAILS	
18	PROPOSED ROADWAY LIGHTING DETAILS	
19	PROPOSED ACCESS ROAD LIGHTING CONTROLLER	1
20	SIGNING PLAN	
21	FENCE STANDARDS	
22	PROPOSED FENCING PLAN	8
23	PROPOSED MARKING PLAN	837-04RDD
24	PROPOSED STORM WATER POLLUTION PREVENTION PLAN & DETAILS	
25	PROPOSED TRAFFIC CONTROL PLAN	837-04RDD
26	PROPOSED STATION CROSS-SECTIONS, STATION 1+00 TO STATION 1+50	
27	PROPOSED STATION CROSS-SECTIONS, STATION 1+75 TO STATION 2+25	e ct
28	PROPOSED STATION CROSS-SECTIONS, STATION 2+50 TO STATION 3+00	HEI Project No.
29	PROPOSED STATION CROSS-SECTIONS, STATION 3+25 TO STATION 3+75	9
30	PROPOSED STATION CROSS-SECTIONS, STATION 4+00 TO STATION 4+50	
31	PROPOSED STATION CROSS-SECTIONS, STATION 4+75 TO STATION 5+00	
32	PROPOSED STATION CROSS-SECTIONS, STATION 5+25 TO STATION 5+50	
33	PROPOSED STATION CROSS—SECTIONS, STATION 5+75 TO STATION 6+25	
34	PROPOSED STATION CROSS-SECTIONS, STATION 6+50 TO STATION 6+63.19	

HANSON Scote NO SCALE DATE 04/16/04

CONSTRUCT T-HANGER
ACCESS ROAD
SUMMARY OF QUANTITIES
INDEX TO SHEETS

2 2 of 34 sheets

FEB 15, 2005 11:36 AM DPE 1:\ARRORTS\STLOUIS\837-04R