(RE	INFORC	ING BA	ARS SCH	HEDULE
TVDE	QUANTITY	DIMENSIONS		CIZC	APPROX. WT. OF
TYPE	PER INLET	Ä	В	SIZE	BARS IN INLET
A	2	3'4"	2'-4"	#5	16.7

INLET NOTES


INLET TO BE CONSTRUCTED OF STRUCTURAL P.C. CONCRETE. THE CONTRACT UNIT PRICE PER INLET SHALL INCLUDE THE FRAME, GRATE AND STEPS IN PLACE AND COMPLETE PER

1/2" CHAMFER TO BE USED ON ALL EXPOSED CORNERS OF INLETS. BARS TO BE INSTALLED 2" FROM FACE OF WALLS.


THE FRAME AND GRATE SHALL BE NEENAH R-3475-E, DEETER 2425-E.

"H" SHALL BE EQUAL TO THE PROPOSED PAVEMENT THICKNESS AND NOT LESS THAN THE ATTACHED MINIMUMS. TYPE A 9" MINIMUM.

INLET STEPS SHALL BE NEENAH R-1980-1. 12" TO 15" C.C. STEPS TO BE INSTALLED WHEN Y IS GREATER THAN 5' COST. THE COST OF THE STEPS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EACH INLET.



INLET TYPE A



"NOT TO SCALE"

MANHOLE NOTES

- MANHOLE TO BE CONSTRUCTED OF STRUCTURAL P.C. CONCRETE. THE CONTRACT UNIT PRICE PER MANHOLE SHALL INCLUDE THE FRAME, LID
- TO THE MANHOLE STRUCTURE.
- TO BE INSTALLED WHEN Y IS GREATER THAN 5'. THE COST OF THE STEPS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EACH

SR083	BA				
	REVISION				
	DATE				
	ST. LOUIS REGIONAL AIRPORT St. Louis Regional				
	HE Project No. 837—04RDD Filesone R—5310RN.DWG Scole NOT TO SCALE Pole 03/08/04 LAYOUT TLW 03/08/04 DRAWN TLW 03/08/04 REVIEWED WJM 06/23/04				
	Hanson Professional Services Inc. 1925 South Study Street Springfield, Illinous 62772-2886 Offices Nationwide				
	CONSTRUCT T-HANGAR ACCESS ROAD PROPOSED DRAINAGE DETAILS				

2. THE FRAME AND LID SHALL BE NEENAH R-3492 OR EQUAL, ANCHORED

3. MANHOLE STEPS SHALL BE NEENAH R-1980-1. 12" TO 15" C.C. STEPS

4. THE PROPOSED MANHOLES WILL BE PAID FOR UNDER THE FOLLOWING: ITEM AR751540 "MANHOLE 4" " _ 1 EACH.

11 of 34 sheet