GENERAL NOTES

- 1. IF SO DIRECTED BY THE ENGINEER, DITCHES ADJACENT TO EMBANKMENTS SHALL BE CONSTRUCTED PRIOR TO STARTING THE CONSTRUCTION OF THE EMBANKMENT FILL.
- 2. THE ALGEBRAIC DIFFERENCE BETWEEN THE PAVEMENT AND SHOULDER SLOPES SHALL NOT EXCEED 8%. THE SHOULDER ON THE OUTSIDE OF SUPER ELEVATED CURVES SHALL BE FLATTENED ACCORDINGLY.
- 3. TREES SHALL BE PRESERVED THROUGHOUT THIS SECTION AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER. GENERALLY, TREES OUTSIDE THE CLEAR ZONE, AND WHICH DO NOT INTERFERE WITH CONSTRUCTION, SHALL NOT BE DISTURBED.
- 4. EARTHWORK COMPACTION SHALL BE TO THE SATISFACTION OF THE ENGINEER.
- 5. ALL PERMANENT PIPE CULVERTS DESIGNATED ON THE PLANS SHALL BE "REINFORCED CONCRETE PIPE CULVERT OR STORM SEWER PIPE" CONFORMING TO THE REQUIREMENTS OF ARTICLE 1040.03.
- 6. NO HARD ELEVATIONS OR PIPE SLOPES ARE SHOWN ON PLANS FOR THE TEMPORARY PIPE CULVERTS AT EACH TRUCK THRNOLIT LOCATION, THE CONTRACTOR SHALL LISE SOUND ENGINEERING JUDGEMENT TO INSTALL CHILVERTS TO THE GENERAL INTENT NOTED ON THE PLANS. MAINTAIN AT LEAST A ONE-FOOT COVER ON ALL CMP PIPE CULVERTS. MATCH EXISTING FLOWLINES AS CLOSELY AS POSSIBLE.
- 7. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING DRAINAGE THROUGHOUT THE CONSTRUCTION OF THIS PROJECT. ALL ROADSIDE DITCHES WITHIN THE CONSTRUCTION LIMITS ARE TO BE CLEANED, HAVE SILT REMOVED AND BE GRADED TO DRAIN AS NEEDED.
- 8. AT ALL LOCATIONS WHERE THE PROPOSED HOT-MIX ASPHALT OR CONCRETE PAVEMENT JOINS AN EXISTING HOT-MIX ASPHALT OR CONCRETE PAVEMENT, A FULL DEPTH SAW JOINT SHALL BE CONSTRUCTED. THE COST OF THIS JOINT WILL BE INCLUDED IN THE COST OF THE TYPE OF PAVEMENT TO BE CONSTRUCTED.
- 9. THIS PROJECT INCLUDES SEVERAL AREAS OF ROADWAY WIDENING. NO "WIDENING" PAY ITEMS ARE INCLUDED HEREIN. ALL WORK SHALL BE PAID FOR AS NOTED WHETHER THE WIDTH OF THE WORK AREAS EXCEEDS SIX FEET OR WHETHER IT IS LESS THAN SIX FEET.
- 10. THE REMOVAL OF BITUMINOUS SURFACING NOT ON A RIGID TYPE BASE REMOVED IN CONJUNCTION WITH THE BASE SHALL BE REMOVED AS EARTH EXCAVATION. THE REMOVAL OF BITUMINOUS SURFACING ON A RIGID TYPE BASE REMOVED IN CONJUNCTION WITH THE BASE SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR PAVEMENT REMOVAL OF THE TYPE SPECIFIED.
- 11. THE FINAL TOP 100MM (FOUR INCHES) OF SOIL IN ANY RIGHT-OF-WAY AREA DISTURBED BY THE CONTRACTOR MUST BE CAPABLE OF SUPPORTING VEGETATION. THE SOIL MUST BE FROM THE 'A' HORIZON (ZERO TO 2' DEEP) OF SOIL PROFILES OF LOCAL SOILS.

- 12. THE CONTRACTOR SHALL SEED ALL DISTURBED AREAS WITHIN THE PROJECT LIMITS.
- 13. (SEEDING LESS THAN 0.5 ACRE OR 0.2 HECTARES) MULCH METHOD II SHALL BE APPLIED OVER ALL SEEDED
- 14. PREVIOUSLY PUG MILLED STOCKPILES OF "TYPE A" OLDER THAN 1 MONTH WILL NOT BE APPROVED FOR USE UNTIL A MOISTURE CHECK IS RUN TO VERIFY MOISTURE CONTENT. MATERIAL SHIPPED TO PROJECTS WITHOUT BEING TESTED WILL NOT BE ACCEPTED.
- 15. EXCEPT FOR THE TOP 75mm (3"), ALL AGGREGATE BASES AND SUBBASES 300mm (12") IN THICKNESS SHALL BE CONSTRUCTED OF AGGREGATE GRADATION CA-2. IF THE SPECIFIED THICKNESS EXEEDS 300mm (12"). THE BASES OR SUBBASES SHALL BE CONSTRUCTED OF TOPSIZE 150mm (6") BREAKER-RUN CRUSHED STONE WITH 70% TO 90% BY WEIGHT PASSING THE 4" SIEVE AND 15% TO 40% BY WEIGHT PASSING THE 50mm (2") SIZE SIEVE. EXCEPT FOR THE TOP 75mm (3"). THE BREAKER-RUN CRUSHED STONE SHALL BE REASONABLY UNIFORMLY GRADED FROM COARSE TO FINE AND BE TAKEN FROM A QUARRY LEDGE CAPABLE OF PRODUCING CLASS "D" QUALITY AGGREGATE. THE TOP 75mm (3") SHALL BE GRADATION CA-6 OR CA-10 REGARDLESS OF THICKNESS. THE WATER NECESSARY TO ACHEIVE COMPACTION IN ALL BUT THE TOP 75mm (3") LAYER MAY BE ADDED AFTER THE SUBBASE OR BASE COURSE IS PLACED ON THE GRADE.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMBERS OF JULIE:

JO-CARROLL ENERGY (ELECTRIC) MISSISSIPPI PALISADES PARK (WATER MAIN)

MISSISSIPPI PALISADES PARK (SANITARY SEWER)

CENTURY LINK (TELEPHONE)

FOLLOWING ARE THE KNOWN UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS WHICH ARE NOT MEMBERS OF JULIE AND SHOULD BE NOTIFIED INDIVIDUALLY

17. THE CONTRACTOR IS ADVISED THAT LITTLE HARD SURVEY DATA WAS OBTAINED FOR THIS PROJECT. MOST INFORMATION WAS EXTRACTED FROM AERIAL SURVEY DATA. TO INSURE THAT THE ROADWAY IS RECONSTRUCTED IN ITS EXISTING LOCATION AND NEAR THE SAME ELEVATION. THE CONTRACTOR SHALL OBTAIN CENTERLINE ELEVATIONS AT A MINIMUM OF ONE HUNDRED FOOT INTERVALS AND SHALL SET OFFSET HUBS AT THE SAME ONE HUNDRED FOOT INTERVALS TO REESTABLISH THE ROADWAY ALIGNMENT AND PROFILE. THIS WORK SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR CONSTRUCTION LAYOUT. IF, IN THE OPINION OF THE RESIDENT ENGINEER, ADDITIONAL OFFSET HURS AND ELEVATIONS ARE NECESSARY TO REESTABLISH THE ROADWAY, THE CONTRACTOR SHALL OBTAIN/SET THESE HUBS AT NO ADDITIONAL COST.

LEGEND

EXISTING SIGN

(0) MANHOLE - 340--CONTOUR

> TIMBER LINE PIPF CULVERT

- IRON ROD
- BENCHMARK

SIGN

Ø STREET LIGHT

GUY WIRE -17-POWER POLE

YARD HYDRANT

YH Q

UNDERGROUND ELECTRIC


OVERHEAD UTILITIES

STORM SEWER EVERGREEN TREE

DECIDUOUS TREE

PROPOSED

PERIMETER EROSION BARRIER



TEMPORARY DITCH CHECK

PRECAST REINFORCED CONCRETE FLARED END SECTION

MANHOLE OR INLET

ABBREVIATIONS

CUBIC YARD

FOUTVALENT ROUND SIZE HORIZONTAL ELLIPTICAL PIPE

PRECAST REINFORCED CONCRETE REINFORCED CONCRETE CULVERT PIPE

STORM WATER POLLUTION PREVENTION PLAN EROSION CONTROL PLAN

THE FOLLOWING PLAN WAS ESTABLISHED AND INCLUDED IN THESE PLANS TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE UNDER NPDES-

THE PURPOSE OF THIS PLAN IS TO MINIMIZE SILTATION WITHIN THE CONSTRUCTION ZONE AND TO ELIMINATE SEDIMENTS FROM ENTERING AND LEAVING THE CONSTRUCTION ZONE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER

CERTAIN ITEMS, AS SHOWN IN THIS PLAN AND REFERENCED BY THE LEGEND, SHALL BE PLACED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE PLACED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION RESULTING FROM THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL PLACE PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A REASONABLE AMOUNT OF TIME: THEREFORE, REDUCING THE AMOUNT OF AREA BEING OPEN TO THE POSSIBILITY OF EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING. THE RESIDENT ENGINEER WILL DETERMINE IF TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED. THE SIZE OF THE PROPOSED DITCH CHECKS. THE PROPER METHOD OF INSTALLATION. AND IF ANY ADDITIONAL TEMPORARY PROSION CONTROL SYSTEMS SHALL BE ADDED WHICH ARE NOT INCLUDED IN THE PLANS. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN IN STANDARD 280001 OF THE PLANS.

SITE DESCRIPTION

DESCRIPTION OF CONSTRUCTION ACTIVITY:

THIS PROJECT CONSISTS OF___ REMOVAL AND RECONSTRUCTION OF THE EXISTING SOUTH SLOPE ROAD AND PARKING AREAS

DESCRIPTION OF INTENDED SEQUENCE OF ACTIVITIES: THE SEQUENCE OF EVENTS ARE AS FOLLOW: CLEARING, EXCAVATION, EMBANKMENT, GRADING AND PAVING. THIS PROJECT WILL BE CONSTRUCTED IN SEGMENTS AS SHOWN IN THE "STAGING PLANS".

TOTAL CONSTRUCTION SITE (CONSTRUCTION LIMIT TO CONSTRUCTION LIMIT) 3.5 ACRES PROPOSED R.O.W (TOTAL PARCEL AREA) N/A ACRES DISTURBED BY EXCAVATION (E.O.P TO CONSTRUCTION LIMIT) 2.1 ACRES SUPPORTING REPORTS AND PLANS THE FOLLOWING ASSISTED IN DEVELOPING THE EROSION CONTROL PLAN AS REFERENCED DOCUMENTS:

USGS DRAINAGE MAPS, PROJECT PLAN DOCUMENTS

DRAINAGE TRIBUTARIES RECEIVING WATER FROM CONSTRUCTION SITE

MISSISSIPPI RIVER

EROSION CONTROLS AND SEDIMENT CONTROL PROCEDURES STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION: PERIMETER EROSION CONTROL SHALL BE PLACED PRIOR TO BEGINNING EARTHWORK.

STABILIZATION PRACTICES DURING CONSTRUCTION: AS EARTH EXCAVATION AND EMBANKMENT ARE BEING COMPLETED THE CONTRACTOR SHALL PLACE DITCH CHECKS. INLET AND PIPE PROTECTION, EROSION CONTROL BLANKET, AND SEEDING AS STAGES OF THE PROJECT ARE COMPLETED. PERIMETER EROSION BARRIER WILL BE INSTALLED AT ADDITIONAL LOCATIONS AS THE PROJECT PROGRESSES. SEEDING SHALL BE COMPLETED AS SPECIFIED IN THE EROSION CONTROL/ SEEDING MOBILIZATION AND TEMPORARY SEEDING SPECIAL PROVISION.

MAINTENANCE AFTER FINAL GRADING

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS SEEDED AND ESTABLISHED WITH THE PROPER STAND. ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP AND DISTURBED TURF RESEEDED.

APPLICATION RATES

GRANULAR MATERIALS BITUMINOUS MATERIAL (PRIME COAT) BITUMINOUS MATERIAL (PRIME COAT) HOT-MIX ASPHALT

NITROGEN FERTILIZER NUTRIENT PHOSPHERUS FERTILIZER NUTRIENT POTASSIUM FERTILIZER NUTRIENT

2-05 TONS/CY 04. GAL/SQ YD OR 0.0016 TON/SY ON AGGREGATE (MC-30)
0.1 GAL/SQ YD OR 0.0004 TON/SY ON HARD SURFACE (RC-70)

112#/IN/SQ YD 90 LB/ACRE 90 LB/ACRE 90 LB/ACRE

DESIGNED IΔW REVISED 01/14/11 STATE OF ILLINOIS DRR REVISED **DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS**

GENERAL NOTES, LEGEND AND SWPPP PLAN NOTES SHEET NO. 8 OF 36 SHEETS STA.

IDOT/IDNR STATEWIDE MISSISSIPPI PALISADES STATE PARK SOUTH SLOPE ROAD

SECTION COUNTY SOUTH SLOPE ROAD CARROLL CONTRACT NO. 46166 REVISED 02/09/10 DRR: 01/25/11 DRE