

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	28					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	300	300				
40600300	AGGREGATE (PRIME COAT)	TON	138	138					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	350	350				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	52	52					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	404	404				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	124	124				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	122	122					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	260	260				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2880	2880					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	260	260				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	34279	34279					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	404	404				
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SO YD	400	400					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	147	147				
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SO YD	550	550					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1415	1415				
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SO YD	300	300					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	344	344													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1													
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4923	4923													
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	110	110													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	32219	32219													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	300	300													
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	350	350													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	404	404													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	124	124													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	11876	11876													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	110	110													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	32219	32219													

* SPECIALTY ITEMS

FILE NAME =	USER NAME = pooltech	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL RTE. 83 (CALUMET SAG RD.) (US 45 TO HIGHWOOD DR.) SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
6:\pw_work\p\p\pooltech\0108793\DI52910-SH-plan.dgn		DRAWN -	REVISED -			344	525-2-RS-1	COOK	19	3	
PLOT SCALE = 50/2000 "/ IN.		CHECKED -	REVISED -			CONTRACT NO. 60K60					
PLOT DATE = 2/1/2011		DATE -	REVISED -			SCALE: NONE SHEET NO. OF SHEETS STA. TO STA. FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					