STATION			WALLS 8A AND 8B				
			20200100		20201200		
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
NORTH SIDE OF I-80			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
870+00.00	TO	870+50.00	0.0	0.0	5.6	0.0	0.0
870+50.00	TO	871+00.00	0.0	0.0	5.6	0.0	0.0
871+00.00	TO	871+50.00	0.0	0.0	5.6	0.0	0.0
871+50.00	TO	872+00.00	0.0	0.0	5.6	0.0	0.0
872+00.00	TO	872+50.00	0.0	0.0	5.6	0.0	0.0
872+50.00	TO	873+00.00	0.0	0.0	5.6	0.0	0.0
873+00.00	TO	873+50.00	0.0	0.0	5.6	0.0	0.0
873+50.00	TO	874+00.00	0.0	0.0	5.6	0.0	0.0
874+00.00	TO	874+50.00	0.0	0.0	5.6	0.0	0.0
874+50.00	TO	875+00.00	0.0	0.0	5.7	0.0	0.0
875+00.00	TO	875+50.00	2.7	2.3	9.3	0.0	2.3
875+50.00	TO	876+00.00	5.2	4.4	12.6	0.0	4.4
876+00.00	TO	876+50.00	5.2	4.4	12.7	0.0	4.4
876+50.00	TO	877+00.00	5.5	4.6	12.7	0.0	4.6
877+00.00	TO	877+50.00	5.4	4.6	13.1	0.0	4.6
877+50.00	TO	878+00.00	5.1	4.3	14.2	0.0	4.3
878+00.00	TO	878+50.00	5.0	4.3	10.9	0.0	4.3
878+50.00	TO	879+00.00	4.9	4.2	7.2	0.0	4.2
879+00.00	TO	879+50.00	4.8	4.1	7.2	0.0	4.1
879+50.00	TO	880+00.00	4.8	4.1	7.2	0.0	4.1
880+00.00	TO	880+50.00	4.9	4.2	7.3	0.0	4.2
880+50.00	TO	881+00.00	5.0	4.3	7.5	0.0	4.3
881+00.00	TO	881+50.00	4.7	4.0	7.5	0.0	4.0
881+50.00	TO	882+00.00	4.8	4.1	7.6	0.0	4.1
882+00.00	TO	882+50.00	5.2	4.4	7.8	0.0	4.4
882+50.00	TO	883+00.00	5.3	4.5	7.9	0.0	4.5
883+00.00	TO	883+50.00	5.5	4.6	8.1	0.0	4.6
883+50.00	TO	884+00.00	5.5	4.6	8.1	0.0	4.6
884+00.00	TO	884+50.00	5.4	4.6	8.0	0.0	4.6
884+50.00	TO	885+00.00	5.2	4.4	7.9	0.0	4.4
885+00.00	TO	885+50.00	4.1	3.5	6.5	0.0	3.5
885+50.00	TO	886+00.00	2.5	2.1	4.4	0.3	1.8
886+00.00	TO	886+50.00	2.6	2.2	4.7	0.3	1.9
886+50.00	TO	887+00.00	4.2	3.5	6.7	0.0	3.5
887+00.00	TO	887+50.00	4.8	4.1	7.4	0.0	4.1
887+50.00	TO	888+00.00	3.9	3.3	6.2	0.0	3.3
888+00.00	TO	888+50.00	3.1	2.7	5.2	0.0	2.7
888+50.00	TO	889+00.00	3.1	2.7	5.2	0.0	2.7
889+00.00	TO	889+35.00	2.2	1.9	3.6	0.0	1.9
TOTALS			130	111	290	1	110

STATION			WALL 11				
			20200100		20201200		
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
NORTH SIDE OF I-80			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
989+10.00	TO	990+00.00	0.0	0.0	11.2	0.0	0.0
990+00.00	TO	990+50.00	0.0	0.0	5.8	0.0	0.0
990+50.00	TO	991+00.00	0.0	0.0	5.6	0.0	0.0
991+00.00	TO	991+50.00	0.0	0.0	5.6	0.0	0.0
991+50.00	TO	992+00.00	0.0	0.0	5.6	0.0	0.0
992+00.00	TO	992+25.00	0.0	0.0	2.8	0.0	0.0
992+25.00	TO	992+50.00	0.0	0.0	2.8	0.0	0.0
992+50.00	TO	992+75.00	0.0	0.0	2.8	0.0	0.0
992+75.00	TO	993+00.00	0.0	0.0	2.9	0.0	0.0
993+00.00	TO	993+50.00	0.0	0.0	5.8	0.0	0.0
993+50.00	TO	994+00.00	0.0	0.0	5.7	0.0	0.0
994+00.00	TO	994+50.00	0.0	0.0	5.7	0.0	0.0
994+50.00	TO	995+00.00	0.0	0.0	5.6	0.0	0.0
995+00.00	TO	995+50.00	0.0	0.0	5.5	0.0	0.0
995+50.00	TO	996+00.00	0.0	0.0	5.5	0.0	0.0
996+00.00	TO	996+50.00	0.0	0.0	5.6	0.0	0.0
996+50.00	TO	997+00.00	0.0	0.0	6.6	0.0	0.0
997+00.00	TO	997+50.00	0.0	0.0	8.5	0.0	0.0
997+50.00	TO	998+00.00	0.0	0.0	8.4	0.0	0.0
998+00.00	TO	998+50.00	0.0	0.0	7.2	0.0	0.0
998+50.00	TO	999+00.00	0.0	0.0	6.3	0.0	0.0
999+00.00	TO	999+50.00	0.0	0.0	5.6	0.0	0.0
999+50.00	TO	1000+00.00	0.0	0.0	5.5	0.0	0.0
1000+00.00	TO	1000+50.00	0.0	0.0	5.4	0.0	0.0
1000+50.00	TO	1001+00.00	0.0	0.0	5.6	0.0	0.0
1001+00.00	TO	1001+50.00	0.0	0.0	5.6	0.0	0.0
1001+50.00	TO	1002+00.00	0.0	0.0	5.6	0.0	0.0
1002+00.00	TO	1002+50.00	0.0	0.0	5.6	0.0	0.0
1002+50.00	TO	1003+00.00	0.0	0.0	5.6	0.0	0.0
1003+00.00	TO	1003+50.00	0.0	0.0	5.4	0.0	0.0
1003+50.00	TO	1004+00.00	0.0	0.0	5.5	0.0	0.0
1004+00.00	TO	1004+50.00	0.0	0.0	5.5	0.0	0.0
1004+50.00	TO	1005+00.00	0.0	0.0	5.5	0.0	0.0
1005+00.00	TO	1005+50.00	0.0	0.0	5.6	0.0	0.0
1005+50.00	TO	1006+00.00	0.0	0.0	5.5	0.0	0.0
1006+00.00	TO	1006+50.00	0.0	0.0	5.5	0.0	0.0
1006+50.00	TO	1007+00.00	0.0	0.0	5.6	0.0	0.0
1007+00.00	TO	1007+50.00	0.0	0.0	5.6	0.0	0.0
1007+50.00	TO	1008+00.00	0.0	0.0	5.6	0.0	0.0
1008+00.00	TO	1008+50.00	0.0	0.0	5.6	0.0	0.0
1008+50.00	TO	1009+00.00	0.0	0.0	5.6	0.0	0.0
1009+00.00	TO	1009+50.00	0.0	0.0	5.6	0.0	0.0
1009+50.00	TO	1010+00.00	0.0	0.0	5.6	0.0	0.0
1010+00.00	TO	1010+50.00	0.0	0.0	5.6	0.0	0.0
TOTALS			0	0	248	0	0

SUMMARY						
	20200100		20201200			
WALL	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
7A AND 7B	204	173	329	0	173	
8A AND 8B	130	111	290	1	110	
11	0	0	248	0	0	
OUTFALL LOCATIONS	34	29	53	7	29	
TOTAL	368	313	920	8	313	

n:\pro\33845_noise walls\design\misc.sheets\33845N-sche803.dgn

ENGINEERING CONSULTANT
Ciorba Group, Inc.
CONSULTING ENGINEERS
5597 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel 773.775.4069 Fax 773.775.4014
Email chicago@ciorba.com

USER NAME = jkjellman	DESIGNED - CRC	REVISED -
	DRAWN - JMK	REVISED -
PLOT SCALE = 1.0000 ' / IN.	CHECKED - SNS	REVISED -
PLOT DATE = 3/24/2011	DATE - 1/7/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.I. 80 NOISE ABATEMENT WALLS
SCHEDULES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99-5R-1	WILL	112	7

CONTRACT NO. 60N86

ILLINOIS FED. AID PROJECT