

N.T.S.

16" MIN. HEIGHT OF FILTER CONSTRUCTION NOTES FOR FABRICATED SILT FENCE WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. 2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION. 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER LAPPED BY 6" AND FOLDED. 4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.

PREFABRICATED UNIT: GOEFAB, ENVIROFENCE OR APPROVED EQUAL.

FENCE:


8' MAX. SPACING (TYP.) EXISTING GRADE -FOOTING STEEL EITHER 'T' OR 'U' TYPE OR 2" HARDWOOD WOVEN WIRE 14 1/2 GA. 6" MAX. MESH OPENING FILTER X, MIRAFI 100X OR STABLINKA T140N WOOD FENCE DETAIL (OR AS SPECIFIED BY THE ENGINEER) NOT TO SCALE

1. ALL MATERIAL SHALL BE SOUTHERN YELLOW PINE IMPREGNATED WITH THE PRESERVATIVE, COPPER NAPHTHENATE (COPPERWOOD OR APPROVED EQUAL).

-1"x6" PICKET (TYP.) - 5"x5" POST (TYP.)

2. FENCE SHALL BE ASSEMBLED BY FACE NAILING.

3. CLASS SI CONCRETE SHALL BE USED CONFORMING TO THE APPLICABLE PORTIONS OF SECTION 1020, EXCEPT THAT IF THE CONCRETE IS MIXED IN TRANSIT MIXERS OR TRANSPORTED IN AGITATOR TRUCKS, THE TIME LIMIT FOR UNLOADING IT MAY BE EXTENDED TO 120 MINUTES BY THE ENGINEER.



FILE NAME **

-	USER NAME =	DESIGNED — MB	REVISED —
		DRAWN - MB	REVISED —
	PLOT SCALE =	CHÉCKED — AJB	REVISED
	PLOT DATE =	DATE - 10/29/2008	REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00098-00-SW	DUPAGE	22	15
 SIDEW	ALK PROJECT	CONTRACT	NO. 6	3132
FED. R	DAD DIST, NO. 1 ILLINOIS FED. A	ID PROJECT		