			CONSTRUCTION CODE					
					IRVI	NG PARK RD BIKE	HIGGINS RD BIKE PATH	
					80% FED	80% FED	80% FED	80% FED
			1		20% LOCAL TRAFFIC SIGNALS	20% LOCAL LIGHTING	20% LOCAL BIKE PATH	20% LOCAL BIKE PATH
C	CODE	ITEM	UNIT	TOTAL	0021	0021	0038	0038
	NO.	1 LIV		QUANTITY	URBAN	URBAN	URBAN	URBAN
873	301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	358	358			
		ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	293	293			
	301225			1	1	:		
875	502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1				
878	800100	CONCRETE FOUNDATION, TYPE A	FOOT	4	4			
879	900200	DRILL EXISTING HANDHOLE	EACH	1	1		,	
881	102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	3	3			
881	102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	1			
888	800100	PEDESTRIAN PUSH-BUTTON	EACH	5	5			
895	502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1			
	000220	TREE, ACER X FREEMANII MARMO (MARMO FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	15			15	
-	003020	TREE, CELTIS OCCIDENTALIS PRAIRIE PRIDE (PRAIRIE PRIDE HACKBERRY), 2-1/2" CALIPER,	EACH	16			16	
		BALLED AND BURLAPPED						
A20	004420	TREE, GINKGO BILOBA (GINKGO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7			7	
	004520	TREE, GINKGO BILOBA PRINCETON SENTRY (PRINCETON SENTRY GINKGO), 2-1/2" CALIPER,	EACH	13			13	
AZ	.004320	BALLED AND BURLAPPED						
	00.4700	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST)	EVCH	8			8	
4 A20	004720		LACIT	J				
		2-1/2" CALIPER, BALLED AND BURLAPPED						
A20	2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	14			14	
4 A20	2008820	TREE, ULMUS CARPINIFOLIA HOMESTEAD HOMESTEAD ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	14		A second	14	
€ B20	2006320	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE	EACH	11				11
		FORM, BALLED AND BURLAPPED		· · · · · · · · · · · · · · · · · · ·				
€ C20	2C11736	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 3' HEIGHT, CONTAINER	EACH	20			20	
×0:	300266	WOODEN FENCE REMOVAL	FOOT	48			48	
	322936	REMOVE EXISTING FLARED END SECTION	EACH	7			7	
	000061	STUMP REMOVAL	EACH	1			1	
	660410	REMOVE RIGHT-OF-WAY MARKERS	EACH	3			3	
	17301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	72	72			
			L SUM	1			0.8	0.2
	0013798	CONSTRUCTION LAYOUT	EACH	1	1			
	0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	FOOT			5 A	200	
	0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH		200			400 △	100 /
	076600	TRAINEES	HOUR	500			400 🔼	100 /

<sup>\*</sup> SPECIALTY ITEMS

 $\triangle$  CONSTRUCTION TYPE - CODE 0042

FILE NAME =	USER NAME = gellwanger	DESIGNED - LP	REVISED -
\D163355-sht-S00.dgn		DRAWN - LP	REVISED -
•	PLOT SCALE = 20.0000 '/ IN.	CHECKED - JP	REVISED -
	PLOT DATE = 1/10/2011	DATE - 10/26/2010	REVISED -

STATE	OF	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION

IRVII	NG PARK ROAD &	HIGGINS	S ROAD B	IKE PATHS	F. R	A.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SUMMARY OF QUANTITIES							07-00091-00-BT	COOK	70	6
SUMMANT OF GOANTITIES						CONTRACT NO. 63355				
SCALE: NONE	SHEET NO. 6 OF 70 SI	HEETS	STA.	TO STA.	F	FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT				

CONSTRUCTION CODE