

# SIDEWALK 6' MIN. (CANOPY — DRIPLINE DESIRED) TREE ROOT PRUNING (EACH TREE) 24" MIN. DEPTH TEMPORARY FENCE 10' (TYP.) BACK OF CURB EDGE OF PAVEMENT


TREE & ROOT PROTECTION

2"x10"x6"(MIN) PLANKS -NO. REQUIRED VARIES W/ SIZE OF TREE (4 MIN)

WIRE RETAINER
NO 6 WIRE (MIN)
WRAP AROUND BOARDS AND
TWIST ENDS TOGETHER
(BEND TWISTED ENDS
TOWARD TREE)


### TREE TRUNK PROTECTION

# DRAINAGE STRUCTURE SPECIAL DETAIL (TO AVOID EXISTING 12" NICOR GAS MAIN)



GUTTER FLAG WIDENING TO BE INCLUDED IN THE COST OF COMB CONC CURB & GUTTER TY B-6.12 (MODIFIED)

## **GUTTER FLAG WIDENING DETAIL FOR** DRAINAGE STRUCTURE SPECIAL



1. ORANGE CONSTRUCTION PROTECTION FENCING (FLUORESCENT POLYETHYLENE LAMINAR SAFETY NETTING OR APPROVED EQUIVALENT) WITH A MINIMUM HEIGHT OF 4 FEET SHALL BE INSTALLED THIS ORANGE CONSTRUCTION FENCING SHALL BE INSTALLED IN ADDITION TO THE


2. STAKES SHALL BE METAL "T" POLES SPACED NO FURTHER THAN 5 FEET ON CENTER. FENCING SHALL BE SECURED TO THE STAKES AT THE TOP AND BOTTOM OF THE STAKE.

3. FENCING SHALL BE INSTALLED AND INSPECTED BY THE ENGINEER PRIOR TO THE ONSET OF ANY CONSTRUCTION OR DEVELOPMENT ACTIVITIES.

4. UNDER NO CIRCUMSTANCES SHALL PROTECTIVE FENCING BE REMOVED WITHOUT APPROVAL FROM THE ENGINEER.

5. NO PERSON SHALL CONDUCT ACTIVITY WITH THE AREAS TO BE PROTECTED. PROHIBITED ACTIVITIES WITHIN THE RESOURCE PROTECTED AREAS SHALL INCLUDE, BUT NOT BE LIMITED TO:

- NO SOLVENTS OR CHEMICALS.
  NO BUILDING MATERIALS OR CONSTRUCTION EQUIPMENT.
  NO GRADE CHANGES, INCLUDING EXCAVATION AND/OR FILLING.
  NO REMOVAL OF VEGETATION FROM THE GROUND UP WITHOUT THE PERMISSION OF THE ENGINEER
  NO SWALES WITHOUT THE PERMISSION OF THE ENGINEER.
  IN INSTANCES WHERE SWALES MUST BE PROPOSED THROUGH PROTECTED AREAS, THE SWALES SHALL BE HAND DUG. MACHINERY OF ANY KIND IS PROHIBITED.
  NO SOIL EROSION CONTROL FENCING WITHIN THE DRIPLINE OF TREES WITHOUT THE PERMISSION OF THE ENGINEER.



LIMIT OF TREE PRUNING -SEE TREE TRUNK PROTECT DETAIL LIMIT OF ROOT PRUNING © OF PIPE EXCAVATED TREE AND ROOT PRUNING SHALL BE DONE IN ACCORDANCE WITH IDOT SPECIFICATION SECTION 201. TREE AND ROOT PRUNING DETAIL

TRFF	DD	TEC	'TIO	NI C	CTAI
INFF	rnı	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	- 8 8 8 7	M 1	

FILE NAME =	USER NAME = MWORMAN	DESIGNED - MCW	REVISED -			CONSTRUCTION DETAILS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEET
N:\CRYSTALLAKE\100316\C1v11\DET02_1003	l6 sht	DRAWN - PMM	REVISED	STATE OF ILLINOIS		PINGREE ROAD	126	08-00107-00-FP	McHENRY	50 24
	PLOT SCALE = 50°	CHECKED - MCW	REVISED -	DEPARTMENT OF TRANSPORTATION		PINGREE RUAD	CONTRACT NO.			
	PLOT DATE = 2/22/2011	DATE -	REVISED -		SCALE:	SHEET NO. 2 OF 7 SHEETS STA. TO STA.		ILLINOIS FED.	AID PROJECT	