

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	71st STREET BRIDGE SN 016- 7721	RETAINING WALLS SN 016- 7722 THRU SN016- 7726	TRAINEES	71st STREET PUMPING STATION
					0004	0008	0040	0042	0043
	X0326671	CONCRETE SURFACE COLOR TREATMENT	SQ FT	10,000	10,000				
*	X0329858	REMOVE AND REINSTALL LUMINAIRE	EACH	12	12				
	X0350810	BOLLARD REMOVAL	EACH	10	10				
*	X0811100	RAILROAD CROSSING	L SUM	1	1				
	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	545	0	545			
	X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	150	150				
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4				
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3				
	X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	251	251				
*	X5090810	PEDESTRIAN RAIL (SPECIAL)	FOOT	150	0	150			
*	X5610708	WATER MAIN REMOVAL, 8"	FOOT	10	10				
*	X5610710	WATER MAIN REMOVAL, 10"	FOOT	40	40				
*	X5610716	WATER MAIN REMOVAL, 16"	FOOT	905	905				
*	X5630008	CUT AND CAP EXISTING 8" WATER MAIN	EACH	5	5				
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2				
	X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	4,818	4,818				
	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
*	X8030110	LOCATING UNDERGROUND CABLE, SPECIAL	EACH	12	12				
*	X8440116	RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	1	1				
*	XX000679	CUT AND CAP EXISTING WATER MAIN	EACH	2	2				
*	XX002185	RELOCATE EXISTING LIGHT POLE	EACH	12	12				
*	XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	9,930	9,930				
*	XX006779	WATER SERVICE LINE 6"	FOOT	152	152				
*	XX007089	VALVE VAULT, 4' DIA., WITH 8" VALVE	EACH	1	1				
*	XX008155	WATER METER VAULT	EACH	1	1				
*	XX008406	8" x 8" TAPPING SLEEVE AND VALVE IN VALVE VAULT, TYPE A, 4 FT-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3				
*	XX008407	16" x 16" TAPPING SLEEVE AND VALVE IN VALVE VAULT, TYPE A, 6 FT-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
*	XX008408	16" x 16" TAPPING SLEEVE AND VALVE IN VALVE VAULT, TYPE A, 6 FT-DIAMETER, SOLID FLAT TOP SLAB	EACH	1	1				
*	XX008409	DUCTILE IRON WATERMAIN, CLASS 52, POLYETHYLENE ENCASEMENT, 16"	FOOT	1,102	1,102				
*	XX008410	DUCTILE IRON WATERMAIN, CLASS 52, POLYETHYLENE ENCASEMENT, NITRILE GASKETS, 8"	FOOT	950	950				
*	XX008411	DUCTILE IRON WATERMAIN, CLASS 52, POLYETHYLENE ENCASEMENT, NITRILE GASKETS, 16"	FOOT	247	247				
*	XX008412	30" DIAMETER STEEL SLEEVE, 0.469" WALL THICKNESS, OPEN CUT	FOOT	65	65				
*	XX008413	30" DIAMETER STEEL SLEEVE, 0.469" WALL THICKNESS, AUGERED	FOOT	155	155				
*	XX008414	VALVE VAULT, 5' DIA., WITH 16" VALVE	EACH	2	2				
	XX008438	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	3	3				
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	10,593	10,593				
	Z0002500	BALLAST DRAINS	FOOT	375	0	375			
	Z0004002	BOLLARDS	EACH	6	6				
	Z0007118	UNTREATED TIMBER LAGGING	SQ FT	26,064	0		26,064		

* DENOTES SPECIALTY ITEM

FILE NAME = P:\62155877\000_CAD\001_Drawing\Sheet\Civil\62155877_sht-500-06.dgn



USER NAME = manuj	DESIGNED - NJH	REVISED -
PLOT SCALE = 1:800' / 1" =	DRAWN - NJH	REVISED -
PLOT DATE = 3/16/2011	CHECKED - TJW	REVISED -
	DATE - March 17, 2011	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE	SHEET NO. 5 OF 6 SHEETS	STA. TO STA.	F.A.U. RTE. 1537	SECTION 06-00050-00-GS	COUNTY COOK	TOTAL SHEETS 209	SHEET NO. 8
			CONTRACT NO. 63556				
			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CRE-9003709				