

GENERAL NOTES

A minimum of 2 air monitors will be required to monitor abrasive blasting operations at each location, see special provision for "Containment and Disposal of Lead Paint Cleaning Residues".

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per LUMP SUM for CLEANING AND PAINTING STEEL BRIDGE NO. 1.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of CLEANING AND PAINTING STEEL BRIDGE NO. 1.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the CLEANING AND PAINTING STEEL BRIDGE NO. 1.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

INDEX OF SHEETS

1. Cover Sheet
2. Summary of Quantities
3. General Notes, Index of Sheets, Standards
4. Traffic Control Plan Structure No. 098-0067
5. Traffic Control Plan Structure No. 098-0072
- Existing Bridge Plans Structure No. 098-0067
6. General Plan & Elevation
7. Superstructure
8. Superstructure
9. Structural Steel
10. Steel Details
- Existing Bridge Plans Structure No. 098-0072
11. General Plan & Elevation
12. Plan & Cross-section
13. Framing Plan
14. Bearings

STANDARDS

- 701101-02 Off-Road Operations, Multilane, 4.5 m (15') to 600 mm (24") From Pavement Edge
- 701301-04 Lane Closure, 2L, 2W, Short Time Operations
- 701400-05 Approach to Lane Closure, Freeway/Expressway
- 701402-08 Lane Closure, Freeway/Expressway, with Barrier
- 701406-06 Lane Closure, Freeway/Expressway, Day Operations Only
- 701901-01 Traffic Control Devices
- 704001-06 Temporary Concrete Barrier
- 720001-01 Sign Panel Mounting Details
- 720006-02 Sign Panel Erection Details
- 720011-01 Metal Posts for Signs, Markers and Delineators
- 728001-01 Telescoping Steel Sign Support
- 729001-01 Applications of Types A and B Metal Posts (For Signs & Markers)

FILE NAME =	USER NAME = linkdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, INDEX OF SHEETS, STANDARDS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D:\BR\Bridg Painting\Contracts\PAINTING	64G28\PLA\eng.dgn	DRAWN -	REVISED -			88	D2 BRIDGE PAINTING 2011-1	WHITESIDE	14	3
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 64G28				
	PLOT DATE = Sat Jan 22 06:48:50 2011	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
						SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____		