SCHEDULE OF QUANTITIES

*A PATCHING SURVEY WAS NOT CONDUCTED FROM STATION 327+00 TO STATION 340+00. QUANTITIES WERE ESTIMATED, BASED ON THE PERCENTAGE OF PATCHING THROUGHOUT THE REMAINDER OF THE SECTION.

FILE NAME =

USER NAME = coombessf

PLOT DATE = 1/7/2011

c:\pw_work\pw1dot\coombessf\d0243364\D570877-sht-schedule.dgn

DESIGNED -

DRAWN

DATE

CHECKED

REVISED

REVISED

REVISED

REVISED

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	44201337 CLASS C PATCHES, TYPE I 9.0" (SQ YD)	44201341 CLASS C PATCHES, TYPE II 9.0" (SQ YD)	44201345 CLASS C PATCHES, TYPE III 9.0" (SQ YD)	44201347 CLASS C PATCHES, TYPE IV 9.0" (SQ YD)	TIE BARS FOR INFO ONLY NO PAYMENT (EACH)									
									STATION 327+00.00 TO STATION 340+00.00				48.0	142.0	34.0	45.0	15.0
									348+00.00	EB	6	11	0.0	7.3	0.0	0.0	0
									350+00.00	ЕВ	6	11	0.0	7.3	0.0	0.0	0
									351+50.00	ЕВ	6	11	0.0	7.3	0.0	0.0	0
									351+50.00	WB	6	11	0.0	7.3	0.0	0.0	0
353+10.00	ЕВ	15	11	0.0	0.0	18.3	0.0	0									
353+10.00	WB	15	11	0.0	0.0	18.3	0.0	0									
353+50.00	ЕВ	4	11	4.9	0.0	0.0	0.0	0									
353+60.00	WB	6	11	0.0	7.3	0.0	0.0	0									
354+00.00	ЕВ	10	11	0.0	12.2	0.0	0.0	0									
354+00.00	WB	10	11	0.0	12.2	0.0	0.0	0									
354+20.00	WB	8	11	0.0	9.8	0.0	0.0	0									
355+00.00	WB	12	11	0.0	14.7	0.0	0.0	0									
355+18.00	ЕВ	4	11	4.9	0.0	0.0	0.0	0									
355+18.00	WB	4	11	4.9	0.0	0.0	0.0	0									
355+95.00	EB	6	11	0.0	7.3	0.0	0.0	0									
355+95.00	WB	6	11	0.0	7.3	0.0	0.0	0									
356+44.00	WB	12	6	0.0	8.0	0.0	0.0	0									
356+93.00	WB	8	11	0.0	9.8	0.0	0.0	0									
357+92.00	EB	8	6	0.0	5.3	0.0	0.0	0									
357+92.00	WB	8	11	0.0	9.8	0.0	0.0	0									
359+90.00	WB	10	11	0.0	12.2	0.0	0.0	0									
362+43.00	EB	8	6	0.0	5.3	0.0	0.0	0									
362+93.00	WB	12	11	0.0	14.7	0.0	0.0	0									
364+91.00	EB	6	6	4.0	0.0	0.0	0.0	0									
364+91.00	WB	6	6	4.0	0.0	0.0	0.0	0									
365+41.00	EB	6	11	0.0	7.3	0.0	0.0	0									
365+41.00	WB	6	11	0.0	7.3	0.0	0.0	0									
365+91.00	ЕВ	15	11	0.0	0.0	18.3	0.0	0									
365+91.00	WB	30	11	0.0	0.0	0.0	36.7	15									
366+30.00	EB	20	11	0.0	0.0	24.4	0.0	10									
				70.7	322.0	113.4	81.7	40.0									

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

COUNTY TOTAL SHEET NO.
PIATT 12 5
CONTRACT NO. 70877

SECTION

(10**,**11)I

1531

TO STA.

SCHEDULE OF QUANTITIES

SHEET NO. OF SHEETS STA.

SCALE: