

SCHEDULE OF QUANTITIES

	LOCATION	WIDTH AT LOCATION	TO	LOCATION	WIDTH AT LOCATION	NUMBER OF LANES	LENGTH (FOOT)	WIDTH (FEET)	AREA (SQ YD)	PAVEMENT GROOVING Z0037300 (SQ YD)
SB	404+57.22	36.0		432+17.42	36.0	3	2760.20	33.0	10120.7	10120.7
SB	432+17.42	36.0		435+18.27	48.0	4	300.85	38.0	1270.3	1270.3
SB	435+18.27	48.0		450+17.42	48.0	4	1499.15	44.0	7329.2	7329.2
SB	450+17.42	48.0		453+61.26	66.0	4	343.84	53.0	2024.8	2024.8
SB	453+61.26	36.0		470+47.07	36.0	3	1685.81	33.0	6181.3	6181.3
SB	470+47.07	56.0		479+95.37	36.0	4	948.30	42.0	4425.4	4425.4
SB	479+95.37	36.0		483+45.	36.0	3	349.63	33.0	1282.0	1282.0
SB	483+45.	56.0		488+20.	48.0	4	475.00	48.0	2533.3	2533.3
SB	488+20.	48.0		489+66.18	48.0	4	146.18	44.0	714.7	714.7
*	489+66.18			492+09.78			243.60	SN 057-0016 (0017)		
SB	492+09.78	48.0		504+37.62	48.0	4	1227.84	44.0	6002.8	6002.8
SB	504+37.62	48.0		510+37.62	36.0	4	600.00	38.0	2533.3	2533.3
SB	510+37.62	36.0		519+67.95	36.0	3	930.33	33.0	3411.2	3411.2
NB	404+57.22	36.0		433+65.07	36.0	3	2907.85	33.0	10662.1	10662.1
NB	433+65.07	36.0		439+65.07	48.0	4	600.00	38.0	2533.3	2533.3
NB	439+65.07	48.0		453+96.88	48.0	4	1431.81	44.0	7000.0	7000.0
NB	453+96.88	48.0		457+98.96	56.0	4	402.08	48.0	2144.4	2144.4
NB	457+98.96	36.0		461+38.17	36.0	3	339.21	33.0	1243.8	1243.8
NB	461+38.17	36.0		471+47.21	56.0	4	1009.04	42.0	4708.9	4708.9
NB	471+47.21	36.0		486+33.9	36.0	3	1486.69	33.0	5451.2	5451.2
NB	486+33.9	66.0		489+63.6	48.0	4	329.70	53.0	1941.6	1941.6
NB	489+63.6	48.0		489+66.18	48.0	4	2.58	44.0	12.6	12.6
*	489+66.18			492+09.78			243.60	SN 057-0016 (0017)		
NB	492+09.78	48.0		502+47.92	48.0	4	1038.14	44.0	5075.4	5075.4
NB	502+47.92	48.0		505+47.92	36.0	4	300.00	38.0	1266.7	1266.7
NB	505+47.92	36.0		519+67.95	36.0	3	1420.03	33.0	5206.8	5206.8
									TOTAL	95,075.6
									ROUNDED	95,100.0

* BRIDGE OMISSION

* F.A.I. 55, F.A.I. 74, & U.S. 51

FILE NAME =	USER NAME = hoganbj	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\hoganbj\d0249155\0570887-sht-Schedule.CEL		DRAWN - ---	REVISED - ---					*	HSIP FY2011-3	MCLEAN	17	16
		CHECKED - ---	REVISED - ---									
		DATE - ---	REVISED - ---			SCALE: -----	SHEET NO. 1 OF 1 SHEETS	STA. -----	TO STA. -----	CONTRACT NO. 70887		
									ILLINOIS FED. AID PROJECT			