CONTRACT: 72D98 SHEET 7 OF 8

PAVEMENT MARKING SCHEDULE				
STATION	TYPE	PAINT PVT MK LINE 5"		
		WHITE	YELLOW	
LT & RT 573+00 TO 641+50	EDGE LINE	12,440 FT		
RT 462+68 TO 468+00	SKIP DASH		130 FT	
LT 462+68 TO 468+00	NO PASS		532 FT	
468+00 TO 494+40	SKIP DASH		660 FT	
LT 494+40 TO 511+10	SKIP DASH		420 FT	
RT 494+40 TO 511+10	NO PASS		1,670 FT	
STA. 511+10 TO 524+88	SKIP DASH		345 FT	
TOTALS		12,440 FT	3,757 FT	

URE REQUIREM	ENTS			
THE FOLLOWING MIXTURE REQUIREMENTS				
PPLICABLE FOR THIS PF	ROJECT			
H.M.A. S.C., MIX C, N70	H.M.A. PATCHING			
PG 64-22	PG 64-22			
4.0% @ N DESIGN = 70	4.0% @ N DESIGN = 70			
IL 9.5 OR 12.5	IL 19.0			
MIX "C"	N/A			
	LOWING MIXTURE REQUI PPLICABLE FOR THIS PE H.M.A. S.C., MIX C, N70 PG 64-22 4.0% @ N DESIGN = 70 IL 9.5 OR 12.5			

NOTES: STATIONS ARE APPROXIMATE.

SCHEDULES
FAP 562 (IL 100)
SECTION (117) RS-7,I
SCOTT COUNTY