

SUMMARY OF QUANTITIES				80% FEDERAL 20% STATE		
				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	SN 080-0003 0014	SN 080-0004 0014	SN 080-0005 0014
50102400	CONCRETE REMOVAL	CU YD	46.6	12.8	14.2	19.6
50157300	PROTECTIVE SHIELD	SQ YD	485	225	96	164
50300100	FLOOR DRAINS	EACH	32	16	16	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	46.6	12.8	14.2	19.6
50300260	BRIDGE DECK GROOVING	SQ YD	1570	486	445	639
50300300	PROTECTIVE COAT	SQ YD	107	29	34	44
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5090	1840	1660	1590
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5520	1460	1680	2380
50800515	BAR SPLICERS	EACH	92	28	32	32
52000110	PREFORMED JOINT STRIP SEAL	FOOT	246	74	74	98
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24	12	6	6
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12		6	6
52100520	ANCHOR BOLTS, 1"	EACH	72	24	24	24
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	2	2	2
67100100	MOBILIZATION	L SUM	1	0.33	0.33	0.34
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	0.5	0.5	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.33	0.33	0.34
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	0.5	0.5	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	12	3	3	6
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1100	343.8	343.8	412.4
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1100	343.8	343.8	412.4
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	7	2	2	3
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1187	340	334	513
* X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	3981	1203.5	1202.5	1575
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	1628	514	455	659
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	36	12	12	12
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1661	521	467	673
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	1628	514	455	659
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	50	16	7	27
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	26	15	11	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	57	18	9	30
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	1	1	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	1	1	2
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.5		0.5

* SPECIALTY ITEM

* (5-2VB-1.5-2HB,5-2VB-2)BR-2

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	327	*	RICHLAND	53	3
		CHECKED -	REVISED -				TO STA.					
		DATE -	REVISED -									
												CONTRACT NO. 74482
												ILLINOIS FED. AID PROJECT