



TOP PLAN (Showing Aluminum Tube)



Hatched area indicates concrete removal at floor drain

Note: Concrete removal and replacement quantities for drains are included in Deck Slab Repair as shown on "Bridge Deck Patching" plan sheets.



Note: See "Bridge Deck Patching" plan sheets for Floor Drain replacement or elimination locations. See "Total Bill of Materials" for each structure for quantities.


Notes: The floor drains shall be painted to match the outside of the fascia beams. Fiberglass pipe shall conform to ASTM D 2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum. Galvanize clamping device according to AASHTO M232. Cost of clamping device and galvanizing is included with Floor Drains.

The exterior surfaces of the floor drains shall be painted with the finish coat as specified in the special provisions for Cleaning and Painting New Metal Structures. The exterior surfaces of the drains shall be cleaned according to Society of Protective Coating's Spec. SSPC-SP1 prior to painting.

COUNTY TOTAL SHEET NO.

Richland 53 16

CONTRACT NO. 74482



PIPE

\*(5-2VB-1,5-2HB,5-2VB-2)BR-2 DESIGNED - KLB REVISED SECTION FILE NAME = USER NAME = swartzrw FLOOR DRAIN DETAIL STATE OF ILLINOIS 482-sht-brdetails-0800003.dq DRAWN KLB REVISED 327 SN. 080-0003 PLOT SCALE = 20.0000 '/ IN. CHECKED -MEA REVISED **DEPARTMENT OF TRANSPORTATION** SHEET NO. 10 OF 15 SHEETS STA. TO STA. REVISED ILLINOIS FED. AID PROJECT PLOT DATE = 1/27/2011 DATE - 12/1/10