

ATE

OT DATE = 2/24/201

12/22/

REVISED

2

TYPICAL END TREATMENT AT SIDEWALK OR MEDIAN

³₄″ ¢ x 8″ Studs Top of sidewalk or median

Shorter plates with a single row of studs at 12" cts. may be necessary on medians which are shallower than 9". See manufacturer's recommendation.

Notes:

The strip seal shall be made continuous and shall have a minimum thickness of ¹4". The configuration of the strip seal shall match the configuration of the Locking Edge Rails. Open or "webbed" strip seal gland configurations are not permitted. The gland shall be sized for a maximum rated movement of 4 inches.

Top of locking

edge rail

The Locking Edge Rails depicted are conceptual only, except for the minimum dimensions shown. The actual configuration of the Locking Edge Rails and matching strip seal may vary from manufacturer to manufacturer. Flange edge rails will not be allowed. Locking Edge Rails may be spliced at slope discontinuities.

The manufacturer's recommended installation methods shall be followed.

The joint opening and deck dimensions detailed on the superstructure are based on a rolled rail expansion joint. If the Contractor elects to use the welded rail expansion joint, the opening and deck dimensions shall be modified according to the dimensions detailed on this sheet. Required modifications shall be made at no additional cost to the State.

All steel components shall be galvanized after fabricatio. according to Article 520.03 of the Standard Specifications Maximum space between rail segments at stage lines shall be $\frac{3}{16}$ ", sealed with a suitable sealant.

Parapet plates and anchorage studs for skews > 30° included in the cost of Preformed Joint Strip Seal.

Grind

Flush

SHEET NO 9 OF 10 SHEETS

BILL OF MATERIAL

110///	Unn	I OT di
Preformed Joint Strip Seal	Foot	308.0

					· · ·
STRIP SEAL	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
058-0111	320	•	Macon	32	31
030-0111			CONTRACT	NO	74491
STA. TO STA.		TULINOIS FED A	D PROJECT		