

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF BEARING AND JOINT REPLACEMENT AND OTHER WORK NECESSARY TO COMPLETE THE PROJECT.

WET REFLECTIVE TEMPORARY TAPE SHALL BE USED DURING STAGE 1 & 2. TEMPORARY PAVEMENT MARKINGS SHALL BE APPLIED AFTER STAGE 2 IS COMPLETED FOR USE UNTIL PERMANENT MARKINGS CAN BE CONSTRUCTED.

THE REFLECTIVE LENS OF ALL RAISED REFLECTIVE PAVEMENT MARKERS IN CONFLICT WITH THE STAGE TRAFFIC CONTROL SHALL BE REMOVED PRIOR TO STAGE 1 CONSTRUCTION. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR RAISED REFLECTIVE PAVEMENT MARKERS, REFLECTOR REMOVAL.

REMOVAL OF THE RAMP NOSES WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE FOOT FOR CONCRETE MEDIAN REMOVAL. REMOVAL OF THE 4" THICK MEDIAN SURFACE WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE FOOT FOR CONCRETE MEDIAN SURFACE REMOVAL. BOTH OF THESE ITEMS SHALL BE CONSTRUCTED ACCORDING TO SECTION 440 OF THE STANDARD SPECIFICATIONS.

THE UNIT PRICE FOR PCC BASE COURSE SHALL INCLUDE THE COST OF REMOVAL OF THAT ITEM AFTER THE COMPLETION OF STAGE 2.

FIELD MARKINGS OF UNDERGROUND UTILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

INDEX OF SHEETS

SHEET NO	TITLE
1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	SCHEDULES
6-12	STAGE 1 CONSTRUCTION DETAILS
13-19	STAGE 2 CONSTRUCTION DETAILS
20-29	STRUCTURAL SHEETS
30-31	MISC. DETAILS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
606301-04	PC CONCRETE ISLANDS AND MEDIANS
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS >= 45 MPH
701606-07	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-07	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & INDEX OF SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca\pwork\pwork\teasleyck\0209780\07	4494-shit-gennote.dgn	DRAWN -	REVISED -			832	*	Clark	3/	2.
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -					CONTRACT NO. 74494		
	PLOT DATE = 2/16/2011	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.