





COVER INLETS WITH STEEL PLATING  
DURING STAGE 2 CONSTRUCTION

**LEGEND**

-  TEMPORARY BRIDGE TRAFFIC SIGNAL
-  IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3
-  TEMPORARY CONCRETE BARRIER
-  STOP BAR

**NOTE:**  
TRAFFIC CONTROL ITEMS NOT SHOWN; INCLUDING SIGNS, DETECTOR LOOPS, TEMPORARY RUMBLE STRIPS AND OTHER ITEMS REQUIRED SHALL BE IN ACCORDANCE WITH HIGHWAY STANDARD 701321-11

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>STAGE 2 TRAFFIC CONTROL</b>			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\swartzw\0242172\d77	507-shr-trafficcontrolstaging.dgn	DRAWN -	REVISED -					677	(15-2,15-1,15,11)RS-1	COLES	43	38
	PLOT SCALE = 20,0000 1/ IN.	CHECKED -	REVISED -		SCALE: 20 SHEET NO. 4 OF 4 SHEETS STA. 350+00 TO STA. 356+00			CONTRACT NO. 74507				
	PLOT DATE = 1/31/2011	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							