INDEX OF SHEETS

COVER PAGE

INDEX OF SHEETS/HIGHWAY STANDARDS/GENERAL NOTES/COMMITMENTS SUMMARY OF QUANTITIES

GENERAL PLAN AND ELEVATION

CONCRETE REMOVAL
CONCRETE DETAILS

BAR SPLICER

FOR INFORMATION SHEET - 1959 APPROACH PAVEMENT STD 2138-1
FOR INFORMATION SHEET - 1984 APPROACH PAVEMENT STD 2324-6
FOR INFORMATION SHEET - 1986 APPROACH PAVEMENT STD 2382-2 (SHT 1 OF 2)
FOR INFORMATION SHEET - 1986 APPROACH PAVEMENT STD 2382-2 (SHT 2 OF 2)

HIGHWAY STANDARDS

000001-06

001001-02

701400-05

701402-08

704001-06

701901-01

GENERAL NOTES

- 1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- 3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING JULLIE. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

 - . BOND MADISON WATER COMPANY
 - . SOUTHWESTERN ELECTRIC COOPERATIVE, INC.

MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY .. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

4. ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.

COMMITMENTS

NONE

SUMMARY OF QUANTITIES

	SUMMARY OF QUANTITIES		TOTAL	CONSTRUCTION TYPE CODE
CODE NO	ITEW	UNIT	QUANTITIES	0014
50102400	CONCRETE REMOVAL	CU YD	35.2	35.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	68.9	68.9
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6240	6240
50800515	BAR SPLICERS	EACH	64	64
67100100	MOBILIZATION	L SUN	1.	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	Z	2
70400100	TEMPORARY CONCRETE BARRIER	FOOT	550	550
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550	550
78000200	THERMOPLASTIC PAVENENT WARKING - LINE	FOOT	3056	3056
78008210	POLYUREA PAVEMENT WARKING TYPE - LINE	FOOT	522	522
78300100	PAVEWENT WARKING REWOVAL	SO FT	1193	1193
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1
70030350	INPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1
		·		
				·]
			,	
	·			
			·	,
	·			
			,	
			·	
		l		l

FILE NAME .	USER NAME = gelinh	DESIGNED	REVISED
cs\p=_work\p=idot\gelinh\d0200025\D876E	5-sht-500.dgn	DRAWN	REVISED
1	PLOY SCALE = 100.0000 ' / IN.	CHECKED	REVISED
	PLOT DATE = 3/4/2011	DATE -	REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

SCALE: .

			F.A.I. SECTION		COUNTY	TOTAL	SHEE!
SUMMARY OF QUANTITIES		70	60-11B-1	WADISON	10	2	
***************************************	T				CONTRACT	NO. 7	76E25
	SHEET NO. 1 OF 1 SHEETS	STA TO STA.	FFO. RC	DAD DIST. NO. ILLINOIS FED.	AID PROJECT		