

GENERAL NOTES

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.

Reinforcement bars designated (E) shall be epoxy coated.

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid

Existing reinforcement shall be cleaned and incorporated into the new construction. Cost included with Concrete Removal.

The Contractor shall ensure the approach slabs and approach shoulders do not settle after removal of the ends of the approaches. If voids are encountered after removal of the deck ends, the Contractor shall pump grout under the approaches to maintain support during removal. Cost included with "Concrete Removal".

INDEX OF SHEETS

- 1) General Plan & Elevation
- 2) Concrete Removal
 3) Concrete Details
- 4) Bar Splicer
- 5) For Information Sheet 1959 Approach Pavement Std 2138-1
- 6) For Information Sheet 1984 Approach Shoulder Std 2324-6
- 7) For Information Sheet 1986 Approach Pavement Std 2382-2 (Sh 1 of 2)
- 8) For Information Sheet 1986 Approach Pavement Std 2382-2 (Sh 2 of 2)

TOTAL BILL OF MATERIAL

	ITEM	UNIT	TOTAL
	Concrete Removal	Cu. Yd.	35.2
Pagas 7W 3rd PH	Concrete Superstructure	Cu. Yd.	68.9
Range 7W 3rd PM	Reinforcement Bars, Epoxy Coated	Pound	6240
Project Location	Bar Splicers	Each	64
水 "			
N			
T 33 T T 38 T 7			
			
OCATION SKETCH			

				1	l		passage .	٨	٨	L			
DESIGNED	John	Uehle	EXAMINED		124	1	7.	J.	L	IJ			_
CHECKED	Brad	Williams			/EN	INEF	R 097 9	TRUC	TUR!	Ħ	ERVIC	ES	
DRAWN	John	Uehle	PASSED	_	W. 1	(. V	12	,	۷۷. کر.	-		
CHECKED	Brad	Williams	<u> </u>		ENGI	NEER	OF BR	IDCES	gNi	0,8	TRUCT	JRES	_

SN 060-0027(EB) & 060-0028(WB) was originally built in 1963 as I-70, Section 60-HB-I.

If consists of dual 3 span continuous WF structures on pile bent abutments, and pile supported solid wall piers.

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

GENERAL PLAN AND ELEVATION STRUCTURE NO. 060-0027 & 0028 SHEET NO. 1 OF 8 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
70	60-11HB-I	MADISON	10	3		
		CONTRACT	NO. 7	6E25		
THE TRIOTS SEED AND DROWSET						