

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 0005		SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 0005	
CODE NO	ITEM	UNIT		LOCATION #1 80% FED 20% STATE	LOCATION #2 80% FED 20% STATE	CODE NO	ITEM	UNIT		LOCATION #1 80% FED 20% STATE	LOCATION #2 80% FED 20% STATE
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	18	6	*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	574.6	465.4	109.2
40600300	AGGREGATE (PRIME COAT)	TON	113	85	28	*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	60863	46782	14081
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3336	2466	870	*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	374	329	45
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1027	533.5	493.5	*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	631	631	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	358.2		358.2	*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	505	444	61
40600990	TEMPORARY RAMP	SQ YD	1390	853	537	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	505	444	61
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6280	4719	1561	80300100	LOCATING UNDERGROUND CABLE	FOOT	60	60	
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	0.5	0.5	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1927	1927	
40800030	AGGREGATE (PRIME COAT)	TON	3.4	2	1.4	20037520	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	92.1		92.1
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	207	125	82	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	60747	48580	12167	X4421000	PARTIAL DEPTH PATCHING	TON	10.3		10.3
44022025	PARTIAL DEPTH REMOVAL 2"	SQ YD	92.1		92.1						
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	3		3						
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	584.7	453	131.7						
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	57.2	57.2							
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	86.2	56.8	29.4						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	505	381	124						
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1792	413	1379						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	GAL	0	0	0						
67100100	MOBILIZATION	L SUM	1	0.5	0.5						
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.5	0.5						
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5						
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.5	0.5						
70300100	SHORT TERM PAVEMENT MARKING	FOOT	103956	47632	56324						
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	574.6	465.4	109.2						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	60863	46782	14081						
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	374	329	45						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	521	521							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	21037	16343	4694						

*SPECIALTY ITEM

FILE NAME *	USER NAME * #USER*	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - ---	REVISED - ---			586	5785-4-157-1-5185-3	MADISON	33	3
		CHECKED - ---	REVISED - ---			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 76E49		
		DATE - -----	REVISED - ---	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT						