

PATCHING SCHEDULE										
LOCATION	LENGTH FOOT	WIDTH FOOT	EAST BOUND	WEST BOUND	FULL DEPTH				PARTIAL DEPTH SOYD	
					TYPE I	TYPE II	TYPE III	TYPE IV		
					SOYD	SOYD	SOYD	SOYD		
LOCATION #1										
STA. 317+70 TO STA. 439+42.53										
	4	12		X		5.3				
	4	12	X			5.3				
	4	12	X	X		*10.7				
	4	12	X	X		*10.7				
	4	12		X		5.3				
	8	12	X			10.7				
	4	12	X			5.3				
	4	12		X		5.3				
	4	12		X		5.3				
	4	12		X		5.3				
	4	12		X		5.3				
	4	12	X			5.3				
	4	12		X		5.3				
	4	12		X		5.3				
	4	12	X			5.3				
	4	12		X		5.3				
	4	12	X	X		*10.7				
	4	12	X	X		*10.7				
	15	12	X				20			
	20	12		X				26.7		
STA. 439+42.53 TO STA. 477+44										
	10	12		X		13.3				
	10	12	X			13.3				
	6	12	X			8				
	6	12		X		8				
	4	12		X		5.3				
	4	12		X		5.3				
	4	12	X			5.3				
	4	12		X		5.3				
	4	12		X		5.3				
	4	12	X			5.3				
	4	12		X		5.3				
	4	12	X			5.3				
	4	12		X		5.3				
	4	12	X			5.3				
	10	12	X	X		*26.6				
	10	12	X	X		*26.6				
	6	12		X		8				
	6	12	X			8				
	12	12	X				16			
	12	12		X			16			
	4	12		X		5.3				
	4	12	X			5.3				
LAKE DR. (NORTH SIDE)										
	15	15						25		
	5	12		X		6.7				
	4	12		X		5.3				
	4	12	X			5.3				
	4	12		X		5.3				
	4	12	X			5.3				
	4	12		X		5.3				
	4	12	X			5.3				
	8	12		X		10.6				
	8	12	X			10.6				
	5	12	X			6.7				
	5	12		X		6.7				
	5	12	X			6.7				
	5	12		X		6.7				
ANTICIPATED FAILURES 10%:					0	41.2	5.2	5.1		
TOTAL:					0	453	57.2	56.8	0	

PATCHING SCHEDULE										
LOCATION	LENGTH FOOT	WIDTH FOOT	EAST BOUND	WEST BOUND	FULL DEPTH				PARTIAL DEPTH TON	PARTIAL DEPTH REMOVAL "2" SOYD
					TYPE I	TYPE II	TYPE III	TYPE IV		
					SOYD	SOYD	SOYD	SOYD		
LOCATION #2										
STA. 6+80 TO STA. 51+10										
	4	12	X			5.3				
	20	12	X					26.7		
	6	12	X			8				
	6	12	X			8				
	4	12	X			5.3				
	4	12	X			5.3				
	4	12	X			5.3				
	4	6	X			2.7				
	6	12	X			8				
	4	12	X			5.3				
	6	12	X			8				
	8	12	X			10.6				
	6	12	X			8				
	6	12	X			8				
	10	12	X			13.3				
	6	12	X			8				
	6	12	X			8				
CORRUGATED MEDIAN										
**EB P.C.C. JOINTS (31 TOTAL)										
	2	12	X						10.3	83.7
ANTICIPATED FAILURES 10%:					0.3	11.97	0	2.67		8.37
SUBTOTAL FROM LOCATION #2:					3	131.67	0	29.37		92.07
TOTAL FROM LOCATION #1:					0	453	57.2	56.8		0
TOTAL:					3.0	585.7	57.2	86.2	10.3	92.1

*QUANTITY IS 2X (EB & WB LANE PATCHING)
 **EASTBOUND PARTIAL DEPTH PATCHING AT EACH P.C.C. JOINT FROM STA. 16+66.82 TO STA. 45+50= 31 TOTAL
 PATCHES ARE TO BE 2' WIDE AND CENTERED OVER THE EACH JOINT.

FILE NAME *	USER NAME = #USER*	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - ---	REVISED - ---			586	578S-4-(57-1.5)BS-3	MADISON	33	7	
	PLOT SCALE = #SCALE*	CHECKED - ---	REVISED - ---			CONTRACT NO. 16E49					
	PLOT DATE = #DATE*	DATE - ---	REVISED - ---			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					