

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	JEFFERSON ROADWAY URBAN	JEFFERSON BRIDGE URBAN
				90% FED 10% STATE	041-0012 (NB) 041-0013 (SB) 90% FED/10% ST
CONSTRUCTION TYPE CODE					
44213204	TIE BARS 3/4"	EACH	32,715	32,715	0003 0014
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	11,349	11,349	
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	28,178	24,974	3,204
48300510	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	SQ YD	47,262	47,262	
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	16,565	16,565	
48301000	PROTECTIVE COAT	SQ YD	92,005	92,005	
50102400	CONCRETE REMOVAL	CU YD	32.1		32.1
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3	
50105220	PIPE CULVERT REMOVAL	FOOT	300	300	
50157300	PROTECTIVE SHIELD	SQ YD	394		394
50300255	CONCRETE SUPERSTRUCTURE	CU YD	32.1		32.1
50300260	BRIDGE DECK GROOVING	SQ YD	1,629		1,629
50300300	PROTECTIVE COAT	SQ YD	81.7		81.7
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2,280		2,280
50500505	STUD SHEAR CONNECTORS	EACH	192		192
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,170		3,170
50800515	BAR SPLICERS	EACH	48		48
52000110	PREFORMED JOINT STRIP SEAL	FOOT	230		230
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	8		8
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	8		8
52100520	ANCHOR BOLTS, 1"	EACH	32		32
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1	
54010504	PRECAST CONCRETE BOX CULVERTS 5' X 4'	FOOT	12	12	
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	40	40	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	474	474	
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	76	76	
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	406	406	
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	307	307	
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	934	934	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	7	7	
54217680	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 24" RISER	EACH	1	1	
54217700	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 24" RISER	EACH	1	1	
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1	
54245205	INLET BOX, STANDARD 542511	EACH	2	2	
54245605	INLET BOX, STANDARD 542536	EACH	2	2	
54245805	INLET BOX, STANDARD 542516	EACH	1	1	
54246205	INLET BOX, STANDARD 542526	EACH	1	1	
54246405	INLET BOX, STANDARD 542531	EACH	1	1	
54248510	CONCRETE COLLAR	CU YD	5	5	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	132	132	
60107600	PIPE UNDERDRAINS 4"	FOOT	37,600	37,600	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	1,752	1,752	
60260100	INLETS TO BE ADJUSTED	EACH	6	6	

FILE NAME =	USER NAME = rollevr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\pwidot\rollavr\d0169788\78172	sht_schedules.dgn	DRAWN -	REVISED -		57	•	Jefferson	422	7				
PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -	SCALE:		SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO.	78172		
PLOT DATE = 2/23/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT										