

PAVEMENT SCHEDULE - STAGE 3

LOCATION STATION TO STATION			COMMENTS	PROCESS MODIFIED SOIL 12"	LIME	STABILIZED SUBBASE**	STABILIZED SUBBASE 4"	PCC SHLDRS 10"	PCC SHLDRS 10 1/2"	PCC SHLDRS 12"	AGG. SHLDRS, TY. A 8"	PVMNT REINF	CRC PVMT 10"	CRC PVMT 10 1/2"	CRC PVMT 12"	PCC PVMT (JOINTED) 10"	PCC PVMT (JOINTED) 10 1/2"	RUBBLIZE PCC PVMT	HMA SURF REM VAR DEPTH	HMA SURFACE REM, 3 1/2"	PAVED SHLDR REM	PVMT REM	
START	TO	END		SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	
636+72.00	TO	640+40.00	SB	1043	31.0		1043			491		491			491						499	511	
640+40.00	TO	651+50.00	SB	1480	44.0		1480					1480			1480								1559
651+50.00	TO	659+34.39	SB	2092	62.1		2092					2092			2092								2089
661+86.48	TO	685+00.00	SB	6169	183.2		6169					6169			6169								6167
685+00.00	TO	692+00.00	SB	2917	86.6		2917			933		1867			1867						951	1855	
692+00.00	TO	695+79.95	SB			293		507				1013	1013							1518			
695+79.95	TO	706+57.19	SB			943		854				4071	4071							4925			
706+57.19	TO	709+53.71	SB			340		197				791	791							1792			
709+53.71	TO	724+00.00	SB VETERAN'S ENT. RAMP	1308	38.9		1308	451								804					453	719	
724+00.00	TO	736+42.22	SB			1114		1928				3857	3857							5804			
736+42.22	TO	739+47.58	SB			957						3313								5020			
739+47.58	TO	740+98.95	SB - STAGE 3A VET. EXIT RAMP	1353	40.2		1353	467										3310			504	745	
740+98.95	TO	756+50.00	SB - STAGE 3A			405		205				814		814		1123		1933		2142			
756+50.00	TO	760+50.00	SB			154		115				693		693				688		809			
760+50.00	TO	762+00.00	SB*			764		1723				6204		6204				8154		4103			
762+00.00	TO	762+00.00	SB* - STAGE 3A			204		444				1638		1638				1084		2188			
762+00.00	TO	762+00.00	SB* - STAGE 3A			37		167				490		490				197		686			
762+00.00	TO	762+00.00	SB			37						200		200				201		201			
762+00.00	TO	762+27.61	SB - STAGE 3A			10		31				18		18						53			
762+00.00	TO	762+27.61	SB			14						114		114						115			
762+27.61	TO	764+00.35	SB - STAGE 3A			61		187										73		300			
762+27.61	TO	764+00.35	SB			155						461		461				843		843			
1+45.00	TO	12+27.87	SB - STAGE 3A IL 15 ENT. RAMP	2106	62.5		2106	1203										722			1223	6594	
1+45.00	TO	12+27.87	SB IL 15 ENT. RAMP	2346	69.7		2346	963										1203			914	1173	
764+00.35	TO	767+50.00	SB			269		466				932		932				935		1398			
767+50.00	TO	777+00.00	SB	3958	117.6		3958		1267			2533		2533							1275	2559	
777+00.00	TO	784+83.31	SB			603		1044				2089		2089				2118		3197			
8+12.00	TO	10+50.00	SB - STAGE 3A IL 15 EXIT RAMP	619	18.4		619	315										265			315	265	
8+12.00	TO	10+50.00	SB IL 15 EXIT RAMP	516	15.3		516	212										264			177	262	
10+50.00	TO	11+67.69	SB - STAGE 3A IL 15 EXIT RAMP			49		157										93		77			
10+50.00	TO	11+67.69	SB IL 15 EXIT RAMP			47		105										131		133			
784+83.31	TO	788+10.10	SB - STAGE 3A			131		435										219		228			
784+83.31	TO	788+10.10	SB			334						871		871				931		1838			
788+10.10	TO	790+00.00	SB - STAGE 3A			76		253				125		125						123			
788+10.10	TO	790+00.00	SB			141						761		761						780			
790+00.00	TO	819+50.00	SB - STAGE 3A			1581		3933				4132		4132				4129		8209			
790+00.00	TO	819+50.00	SB			727						3933		3933				4085		4085			
819+50.00	TO	821+00.00	SB - STAGE 3A	425	12.6		425		200			200		200							200	347	
819+50.00	TO	821+00.00	SB	200	5.9		200					200		200								200	
821+00.00	TO	828+17.95	SB - STAGE 3A	2034	60.4		2034		957			957		957							957	1270	
634+10.00	TO	645+00.00	NB	2854	84.8		2854	1215	243			1456		1456							1241	954	
645+00.00	TO	646+49.11	NB	389	11.6		389		169	34											19		
STAGE 3 TOTAL				31,809	944.8	9,446	31,809	3,937	14,081	5,232	277	53,965	9,732	26,788	17,445	1,526	6,189	31,042	0	51,423	8,728	27,269	

\*NO RUBBLIZATION OR SUBBASE ON AUXILLARY LANE AND 10' OUTSIDE SHOULDER  
 \*\*QUANTITY CALCULATED ASSUMING 3" THICKNESS PLUS A 10% CONTINGENCY FACTOR

PAVEMENT SCHEDULE - STAGE 4

LOCATION STATION TO STATION			COMMENTS	PROCESS MODIFIED SOIL 12"	LIME	STABILIZED SUBBASE	STABILIZED SUBBASE 4"	PCC SHLDRS 10"	PCC SHLDRS 10 1/2"	PCC SHLDRS 12"	AGG. SHLDRS, TY. A 8"	PVMNT REINF	CRC PVMT 10"	CRC PVMT 10 1/2"	CRC PVMT 12"	PCC PVMT (JOINTED) 10"	PCC PVMT (JOINTED) 10 1/2"	RUBBLIZE PCC PVMT	HMA SURF REM VAR DEPTH	HMA SURFACE REM, 3 1/2"	PAVED SHLDR REM	PVMT REM	
START	TO	END		SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	
636+72.00	TO	640+40.00	SB - MIDDLE 12' LANE	491	14.6		491					491			491							491	
640+40.00	TO	651+50.00	SB - MIDDLE 12' LANE	1880	55.8		1880					1880			1880								1880
821+00.00	TO	828+17.95	SB - INSIDE SHLDR & 2 - 12' LANES	2832	84.1		2832		798	160		1915			1915						668	1610	
634+10.00	TO	636+10.00	NB - RIGHT 2 LANES	533	15.8		533					533			533							533	
636+10.00	TO	645+00.00	NB - MIDDLE LANE	1187	35.2		1187					1187			1187							1187	
645+00.00	TO	648+80.00	NB - MIDDLE LANE(LT EXIST. LANE)	507	15.0		507					507			507							507	
STAGE 4 TOTAL				7,430	220.5	0	7,430	0	0	798	160	6,513	0	0	6,513	0	0	0	0	0	0	668	6,208
TOTAL STAGES 1-4				142,602	4,234.9	17,933	142,602	24,039	44,766	16,565	7,940	146,448	27,223	72,869	46,356	3,304	11,378	55,661	7,659	94,169	48,766	55,586	

FILE NAME =	USER NAME = rollavr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT SCHEDULE</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cn:\pw\work\p\idat\rollavr\08169788\78172	gnt_schedules.dgn	DRAWN -	REVISED -		57	*	Jefferson	422	18				
PLOT SCALE = 50,0000' / IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 78172				
PLOT DATE = 2/17/2011		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								