

# GUARDRAIL SCHEDULE

SOUTHBOUND LANE														
	LOCATION STATION TO STATION			GUARDRAIL REMOVAL	SPBGR TYPE A	TRAFFIC BARRIER TERMINAL			PCC SHLDRS 10"	PCC SHLDRS 10 1/2"	GUARDRAIL MARKERS	VERTICAL ADJUSTMENT	TERMINAL MARKERS DIRECT APPLIED	COMMENTS
						TY 1, SPL (TAN)	TYPE 2	TYPE 6						
	STA.	TO	STA.	FOOT	FOOT	EACH	EACH	EACH	SQ YD	SQ YD	EACH	FOOT	EACH	
RIGHT	645+55	TO	650+45		388	2			163.3		5		2	
RIGHT	647+95	TO	650+34		175	1	1			4		1	STAGE 3 & 3A TO BE REMOVED WHEN WORK COMPLETE	
RIGHT	653+87	TO	659+36	569	475	1		1		6		1	STAGE 2 & 2A TO BE REMOVED WHEN WORK COMPLETE	
RIGHT	674+04	TO	677+01	15	250	1			99.0	4		1		
RIGHT	719+50	TO	725+02		450	2			250.0	6		2		
RIGHT	736+67	TO	744+18	351	650	2				6		2		
LEFT	740+32	TO	742+95								263			
RIGHT	769+26	TO	775+01	303	575	2				6		2		
LEFT	771+50	TO	775+40	294	325	1	1			5		1		
RIGHT	786+97	TO	791+47		350	2				5		2		
LEFT	817+38	TO	828+58	1114	1080	1		1		7		1		
RIGHT	822+47	TO	825+21		175	2				4		1	STAGE 3 & 3A TO BE REMOVED WHEN WORK COMPLETE	
LEFT/RT	829+96			86.5				2					SN 041-0013	
<b>TOTAL SB LANES</b>				<b>2,733</b>	<b>4,893</b>	<b>17</b>	<b>2</b>	<b>4</b>	<b>512</b>	<b>1,796</b>	<b>58</b>	<b>263</b>	<b>16</b>	

NORTHBOUND LANE														
LEFT OR RIGHT	LOCATION STATION TO STATION			GUARDRAIL REMOVAL	SPBGR TYPE A	TRAFFIC BARRIER TERMINAL			PCC SHLDRS 10"	PCC SHLDRS 10 1/2"	GUARDRAIL MARKERS	VERTICAL ADJUSTMENT	TERMINAL MARKERS DIRECT APPLIED	COMMENTS
						TY 1, SPL (TAN)	TYPE 2	TYPE 6						
	STA.	TO	STA.	FOOT	FOOT	EACH	EACH	EACH	SQ YD	SQ YD	EACH	FOOT	EACH	
LEFT	696+68	TO	700+50	351	313	1	1		212.2		5		1	
RIGHT	698+00	TO	700+54								253			
LEFT	719+31	TO	723+10		313	1	1		210.6		5		1	
LEFT	754+23	TO	756+63		175	1	1			4		1		
LEFT	756+52	TO	758+91	240	175	1	1			4		1	STAGE 3 & 3A TO BE REMOVED WHEN WORK COMPLETE	
RIGHT	768+23	TO	772+63	338	325	1	1			5		1		
LEFT	769+03	TO	773+17	303	350	1	1			5		1		
RIGHT	816+27	TO	828+58	1286	1138	1		1		7		1		
LEFT	820+29	TO	823+19	52	225	1	1			4		1		
LEFT	825+39	TO	828+58	243	318	1		1		5		1		
LT/RT	829+89			86.5				2					SN 041-0012	
<b>TOTAL NB LANES</b>				<b>2,900</b>	<b>3,331</b>	<b>9</b>	<b>7</b>	<b>4</b>	<b>423</b>	<b>701</b>	<b>44</b>	<b>253</b>	<b>9</b>	
<b>TOTAL =</b>				<b>5,632</b>	<b>8,223</b>	<b>26</b>	<b>9</b>	<b>8</b>	<b>935</b>	<b>2,496</b>	<b>102</b>	<b>516</b>	<b>25</b>	

# SEEDING & EROSION CONTROL SCHEDULE

LOCATION STATION TO STATION	SEEDING, CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	SEEDING, CLASS 7	TEMPORARY DITCH CHECKS	REMARKS
	ACRE	POUND	POUND	POUND	TON	ACRE	SQ YD	POUND	FOOT	EACH	ACRE	FOOT	
MEDIAN STA 641+50 TO 722+50	4.6	819	410	410	9.1	9	2683	1365	3500	5	4.6	96	
MEDIAN STA 722+50 TO 772+00	5.3	950	475	475	10.6	11	3300	1584		10	5.3	150	
MEDIAN STA 772+00 TO 828+50	5.4	974	487	487	10.8	11	3083	1623		5	5.4	84	
LEFT STA 641+50 TO 722+50	3.2	583	292	292	6.5	6	2756	972		175	3.2	80	LEFT = SOUTHBOUND SIDE
LEFT STA 722+50 TO 772+00	4.7	839	419	419	9.3	9	3689	1398		1025	4.7	200	
LEFT STA 772+00 TO 828+50	6.1	1096	548	548	12.2	12	2755	1827		3425	6.1	208	
RIGHT STA 641+50 TO 722+50	4.1	738	369	369	8.2	8	2400	1230		675	4.1	64	RIGHT = NORTHBOUND SIDE
RIGHT STA 722+50 TO 772+00	5.1	918	459	459	10.2	10	2889	1530		1750	5.1	184	
RIGHT STA 772+00 TO 828+50	5.5	983	491	491	10.9	11	3067	1638		1300	5.5	144	
<b>TOTAL</b>	<b>44</b>	<b>7900</b>	<b>3950</b>	<b>3950</b>	<b>88</b>	<b>88</b>	<b>26600</b>	<b>13200</b>	<b>11850</b>	<b>20</b>	<b>44</b>	<b>1210</b>	

FILE NAME =	USER NAME = rollavr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GUARDRAIL AND SEEDING &amp; EROSION CONTROL SCHEDULES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
or:\pw\work\p\midot\rollavr\d8169788\78172	sht_schedules.dgn	DRAWN -	REVISED -			57	*	Jefferson	422	22	
PLOT SCALE = 58.0000' / IN.	CHECKED -	REVISED -	REVISED -			CONTRACT NO. 78172					
PLOT DATE = 2/22/2011	DATE -	REVISED -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.			