

## TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION		PAVEMENT MARKING TAPE, TYPE III, 4"			WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER
		LINE 4"				
		SKIP DASH WHITE	SOLID WHITE	SOLID YELLOW		
		FOOT	FOOT	FOOT		
					SQ FT	EACH
STAGE I						
SB	629+50.0	TO	636+60.0		710.0	9
SB	636+60.0	TO	828+25.0	4791.3	14373.8	240
SB	828+25.0	TO	839+50.0		1125.0	14
SB	839+50.0	TO	856+00.0		1100.0	
STAGE II						
NB	613+50.0	TO	621+25.0		516.7	
NB	621+25.0	TO	628+30.0		705.0	9
NB	628+30.0	TO	629+30.0		66.7	
NB	629+30.0	TO	634+10.0		160.0	
NB	634+10.0	TO	822+50.0		12560.0	
NB	746+00.0	TO	765+00.0		1266.7	
NB	771+00.0	TO	822+50.0		3433.3	
STAGE IIA						
NB	752+00.0	TO	765+00.0		866.7	
NB	772+00.0	TO	822+50.0		3366.7	
STAGE III						
NB	619+50.0	TO	621+10.0		53.3	
NB	626+00.0	TO	821+00.0	4875.0	14625.0	244
NB	701+00.0	TO	707+00.0		400.0	
SB	634+60.0	TO	839+50.0	5122.5	15367.5	281
SB	753+00.0	TO	772+30.0		1286.7	
SB	781+50.0	TO	826+00.0		2966.7	
STAGE IIIA						
SB	757+00.0	TO	772+30.0		1020.0	
SB	781+50.0	TO	825+00.0		2900.0	
STAGE IV						
NB	627+00.0	TO	817+75.0		12716.7	
SB	636+75.0	TO	839+50.0		13516.7	
STAGE V						
SB	826+90.0	TO	839+50.0	315.0	945.0	16
SB	839+50.0	TO	856+00.0		1100.0	
NB	805+03.0	TO	815+03.0		666.8	
NB	815+03.0	TO	820+03.0		333.3	
NB	820+03.0	TO	828+33.0		553.3	
NB	824+39.0	TO	828+33.0		262.7	2
NB	828+33.0	TO	833+77.0		544.0	7
STAGE VI						
SB	826+90.0	TO	839+50.0	315.0	945.0	16
SB	839+50.0	TO	856+00.0		1100.0	
NB	805+03.0	TO	815+03.0		666.8	
NB	815+03.0	TO	828+33.0		886.7	
NB	825+04.0	TO	828+33.0		219.3	
NB	828+33.0	TO	830+00.0		222.7	5
NB	830+00.0	TO	833+12.0		312.0	1
<b>TOTALS</b>				<b>15,419</b>	<b>168,824</b>	<b>844</b>
					<b>341,581</b>	

## TEMPORARY CONCRETE BARRIER

STAGE	LOCATION STATION TO STATION			TEMP CONCRETE BARRIER FOOT	RELOCATE TEMP CONC BARRIER FOOT	IMPACT ATTENUATORS		
	STA.	TO	STA.			TEMP (NON-RED) TEST LEVEL 3	RELOCATE (NON RED) TEST LEVEL 3	
						EACH	EACH	
1	636+65.0	SB	TO	830+15.0	SB	19350.0	1	
2	653+40.0	SB	TO	817+02.5	SB			1
2A	756+32.2		TO	756+52.2	NB	16362.5	1	
3	630+15.0	NB	TO	823+02.5	NB	19287.5		1
3	635+00.0	SB	TO	653+50.0	SB	1787.5		
3A	824+00.0	SB	TO	830+00.0	SB	600.0		1
4	630+30.0	NB	TO	649+30.0	NB	1900.0		1
4	636+47.5	SB	TO	652+60.0	SB	1612.5		1
4	820+45.0	SB	TO	831+45.0	SB	1100.0		1
BRIDGE 1	825+83.0	NB	TO	830+33.0	NB	450.0		1
BRIDGE 1	827+24.0	SB	TO	832+74.1	SB	550.0		1
BRIDGE 2	826+08.0	NB	TO	830+33.0	NB	425.0		1
BRIDGE 2	827+24.0	SB	TO	832+99.0	SB	575.0		1
<b>TOTAL</b>				<b>21,737.5</b>	<b>42,325.0</b>	<b>2</b>	<b>10</b>	

## TEMPORARY PAVEMENT SCHEDULE

LOCATION	TEMPORARY PAVEMENT	PAVEMENT REMOVAL
	SY	SY
SOUTH SB XOVER (XOVER 3)	1412	1412
SOUTH NB XOVER (XOVER 4)	1034	1034
IL 15 XOVER NB STAGE 2 (XOVER 5)	895	895
IL 15 XOVER NB STAGE 2A (XOVER 6)	629	629
IL 15 XOVER SB STAGE 3 (XOVER 7)	697	697
IL 15 XOVER SB STAGE 3A (XOVER 8)	697	697
NORTH SB XOVER (XOVER 1)	2270	2270
NORTH NB XOVER (XOVER 2)	1222	1222
<b>TOTAL</b>	<b>8856</b>	<b>8856</b>

## EMERGENCY MEDIAN CROSSOVER

LOCATION	AGGREGATE SHOULDERS TYPE A, 8"
STA.	SY
665+50.00	192
673+00.00	186
683+50.00	265
691+80.00	299
704+00.00	306
721+50.00	300
737+50.00	305
749+30.00	305
761+45.00	309
776+40.00	316
785+75.00	313
801+00.00	313
<b>TOTAL</b>	<b>3409</b>