

BM 405 - CUT "□" ON NE CORNER OF LIGHT POLE #12, FOUND WEST OF SB LANE I-57/64 & NORTH OF IL 15, ELEV. 489.463
 BM 351 - CHISELED "□" IN E CONC OF OVERHEAD SIGN, FOUND EXIT 95 IL 15, 1ST OVERHEAD SIGN N/ OF IL 15 AT STA 789+21, 30' EOP, ELEV. 482.239

EXIST. CURVE RAMP A1
 PI STA. = 10+64.46
 $\Delta = 25^\circ 46' 01''$ (LT)
 $D = 7^\circ 31' 05''$
 $R = 762.10'$
 $T = 174.31'$
 $L = 342.73'$
 $E = 19.68'$
 T.R. =
 S.E. RUN =
 P.C. STA. = 8+90.15
 P.T. STA. = 12+32.88

PRECAST CONCRETE BOX CULVERTS, 5'x4'
 BOX CULVERT END SECTIONS, CULVERT NO 1
 USFL 474.88'
 DSFL 474.86'
 STONE DUMPED RIPRAP, CLASS A4

PROPOSED STEEL-PLATE BEAM GUARDRAIL, TYPE A
 TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT

MEDIAN DITCH CHECK
 STA 785+75

EMERGENCY MEDIAN CROSSOVER
 (SEE SHEET 155 OF 422 FOR DETAILS)

MEDIAN DITCH CHECK
 STA 785+77
 ELEV 483.25

INLETS TO BE ADJUSTED
 ELEV 481.95

PROPOSED PORTLAND CEMENT CONCRETE SHOULDERS, 10 1/2"

TEMPORARY DITCH CHECK

MOUNT VERNON

VINEYARD

FILE NAME =	USER NAME = rollavr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN 157	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pwwork\pwwork\rollavr\0169788\78172	shlt-pln.dgn	DRAWN -	REVISED -			57	.	Jefferson	422	113	
PLOT SCALE = 50.0000' / 1IN.		CHECKED -	REVISED -			CONTRACT NO. 78172		ILLINOIS FED. AID PROJECT			
PLOT DATE = 2/22/2011		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.			