## INDEX OF SHEETS

SHEET NO.	DESCRIPTION				
1	COVER SHEET				
2	SIGNATURE BLOCK				
3	INDEX OF SHEETS; HIGHWAY STANDARDS; STRUCTURE RATINGS; GENERAL NOTES				
4	TYPICAL SECTION				
5	SUMMARY OF QUANTITIES				
6	SCHEDULES: RESURFACING: THERMOPLASTIC PAVEMENT MARKING				
7	LOCATION MAP FAP 869 / IL 14				
8 - 11	PLAN SHEETS				

## HIGHWAY STANDARDS

701306-03 701311-03 701901-01 780001-02 781001-03

## GENERAL NOTES

THE AGGREGATE TO BE USED IN THE MICRO-SURFACING SHALL BE TYPE II APPLIED AT 16 LB/SQ YD PER PASS.

BITUMINOUS MATERIAL (PRIME COAT) SHALL BE APPLIED PRIOR TO PLACING THE FIRST PASS OF MICRO-SURFACING AT A RATE OF 0.05 - 0.10 GAL/SQ. YD.

THE QUANTITY OF SHORT TERM PAVEMENT MARKING SHOWN IN THE PLANS WAS BASED ON ONE APPLICATION EACH FOR 1 LAYER OF THE PRIME COAT AND 1 LAYER OF SURFACE TREATMENT.

PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS THE RESIDENT ENGINEER SHOULD CONTACT THE BUREAU OF OPERATIONS AND ARRANGE FOR INSPECTION AND APPROVAL OF THE PAVEMENT MARKING LAYOUT.

THE CONTRACTOR SHALL PRESERVE EXISTING STAMPED STATIONING.

THE CONTRACTOR SHOULD FOLLOW THE EXISTING HOT-MIX LAYOUT AS CLOSELY AS POSSIBLE. EACH INDIVIDUAL LANE SHOULD BE DONE EDGE TO EDGE IN ONE PASS. SHOULDERS SHALL BE DONE SEPARATELY.

THE FRICTION AGGREGATE SHALL BE MIXTURE D.

## STRUCTURE RATINGS

STRUCTURE NO.	INV. RATING	OPER. RATING	SUFF. RATING
FAP 869 (IL 14)	- PERRY COUNTY		
073-7020	NA .	NA	100
073-7021	NA	NA	100

FILE NAME =	USER NAME = mocordkr	DESIGNED	REVISED -
c:\pw_work\pwidot\mccordkr\d0239288\782	27-sht-plan.dgn	DRAWN	REVISED
,	PLOT SCALE = 100.0000 '/ IN.	CHECKED	REVISED
	PLOT DATE = 1/24/2011	DATE	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INDEX_OF_SHEETS; GENERAL NOTES							
STRUCTURE_RATINGS							
CHEET	NO	OF	CHECTE	STA	T	O CTA	

AP.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
869	09_PAYI_PRESERY_2011:2	PEB8Y	-11-	3_		
CONTRACT NO. 78227						
ILL INGIS EFO. AID PROJECT						