SUMMARY OF QUANTITIES

	CONSTRUC		IS; 50% MISSOURI CTION TYPE CODE 0014 EXANDER	
			SN 002-0005	
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	
50102400	CONCRETE REMOVAL	CU YD	3.1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.1	
52000365	NEOPRENE EXPANSION JOINT 6 1/2"	FOOT	21.5	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	
67100100	MOBILIZATION	L SUM	1	
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	4	
Z0001901	JACK AND REPOSITION BEARINGS	EACH	2	
Z0001905	STRUCTURAL STEEL REPAIR	POUND	39,960	
Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	41	

GENERAL NOTES

- 1) IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 101.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
- 2) COMMITMENTS: NONE AS OF FEBRUARY 14, 2011.

STANDARDS

STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS 000001-06

AREAS OF REINFORCEMENT BARS 001001-02

INDEX OF SHEETS

COVER SHEET

INDEX OF SHEETS, GENERAL NOTES, STANDARDS, SUMMARY OF QUANTITIES

3-8 ORIGINAL PLAN DETAILS

9-22 STRUCTURE PLANS

reparea	BA:
---------	-----

Goe 3 Jankeining DISTRICT STUDIES & PLANS ENGINEER

Examined By:

DISTRICT LAND ACQUISITION ENGINEER

Examined By:

Carrie Rolson DISTRICT PROGRAM DEVELOPMENT ENGINEER

Examined By:

DISTRICT OPERATIONS ENGINEER

Examined By:

DISTRICT CONSTRUCTION ENGINEER

Examined By:

DISTRICT MATERIALS ENGINEER

Approved By:

FEB 18

DATE

COUNTY TOTAL SHEE NO. F.A.S. RTE. SECTION (138D-BR)I-6 ALEXANDER 22 CONTRACT NO. 78250

STANDARDS AND SUMMARY OF QUANTITIES SHEET NO. OF SHEETS STA.

INDEX OF SHEETS, GENERAL NOTES,

DESIGNED REVISED TLE NAME = JSER NAME = dickersonlm REVISED DRAWN 2-0005-sht-plan.dgn PLOT SCALE = 50.0000 '/ IN. CHECKED REVISED REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

STATE FUNDING