

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0011

ITEM NO.	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
1	20700220	POROUS GRANULAR EMBANKMENT	CU YD	151
2	25100630	EROSION CONTROL BLANKET	SQ YD	5,405
3	28000250*	TEMPORARY EROSION CONTROL SEEDING	POUND	112
4	28000305*	TEMPORARY DITCH CHECKS	FOOT	134.5
5	28000400	PERIMETER EROSION BARRIER	FOOT	24
6	28000500	INLET AND PIPE PROTECTION	EACH	1
7	28100109	STONE RIPRAP, CLASS A5	SQ YD	502
8	28200200	FILTER FABRIC	SQ YD	502
9	31101000*	SUBBASE GRANULAR MATERIAL, TYPE B	TON	1,092
10	40600100*	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	733
11	40603080*	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	440
12	40603310*	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	123
13	48101498*	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	506
14	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
15	50800105	REINFORCEMENT BARS	POUND	27,960
16	51500100	NAME PLATES	EACH	1
17	54003000	CONCRETE BOX CULVERTS	CU YD	166.4
18	54200235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	30
19	54213885	STEEL END SECTIONS 30"	EACH	2
20	67100100	MOBILIZATION	L. SUM	1
21	X0323013*	TUBULAR STEEL GATE	EACH	1
22	X2020410*	EARTH EXCAVATION (SPECIAL)	CU YD	2,000
23	X2501000*	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.12
24	X4020700*	AGGREGATE SURFACE COURSE, TYPE B 8"	SQ YD	94
25	X5121800*	PERMANENT STEEL SHEET PILING	SQ FT	2,088
26	X6650200*	WOVEN WIRE FENCE SPECIAL	FOOT	575
27	X7010216*	TRAFFIC CONTROL AND PROTECTION SPECIAL	L. SUM	1

* INDICATES SPECIAL PROVISION, GENERAL NOTE, OR DETAIL

FILE = S:\PROJECTS\2010\1120010_Stephenson_Co_Bolton_Rd\DESIGN\STRUCT\1120010\Quantities.dgn

REV.	DATE	BY	REMARKS

DRAWN R.D.A.
CHECKED M.A.C.
APPROVED B.K.C.

STEPHENSON COUNTY
CULVERT REPLACEMENT
F.A.S. 78 (N. BOLTON ROAD) OVER PRESTON CREEK
2010

SUMMARY OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.S. 78	10-06118-00-BR	Stephenson	18	2
STA. 17+00.00 - STA. 23+00.00				
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT ER-0177(038)		