07-00099-00-BR MORGAN FED. ROAD DIST. NO. 7 ILLINOIS CONTRACT NO. 9 3 5 4

INDEX OF SHEETS

SHEET NO. DESCRIPTION

- COVER SHEET
- GENERAL NOTES. TYPICAL SECTIONS. 2. PAVEMENT DESIGN INFORMATION
- DETAILS, SUMMARY OF QUANTITIES
- SCHEDULES OF QUANTITIES
- TRAFFIC CONTROL PLAN
- STORM WATER POLLUTION PREVENTION PLAN
- PLAN AND PROFILE 7. -8.
- STRUCTURE PLANS 9. -20.
- 21. -48. CROSS SECTIONS

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** PLANS FOR PROPOSED **HIGHWAY BRIDGE PROGRAM MORGAN COUNTY** SECTION 07-00099-00-BR F.A.S. 609 (CH 28) OVER HENRY CREEK PROJECT NO. BRS-0609(109)

REQUIRED HIGHWAY STANDARDS

000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

280001-05 TEMPORARY EROSION CONTROL SYSTEMS

515001-03 NAME PLATE FOR BRIDGES

630001-09 STEEL PLATE BEAM GUARDRAIL

SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS 630301-05

TRAFFIC BARRIER TERMINAL, TYPE 6A 631032-06

REFLECTOR AND TERMINAL MARKER PLACEMENT 635006-03

REFLECTOR MARKER AND MOUNTING DETAILS 635011-02


TRAFFIC CONTROL DEVICES 701901-01

TYPICAL PAVEMENT MARKINGS 780001-02

TYPICAL APPLICATION OF TRAFFIC CONTROL
DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS BLR 21-8

PLAN PROFILE HORIZ. PROFILE VERT. CROSS SECTIONS HORIZ. CROSS SECTIONS VERT.

JOB NUMBER C-96-205-11



EXISTING STRUCTURE 069-3003 THREE SPAN REINFORCED CONCRETE DECK ON STEEL STRINGERS SUPERSTRUCTURE ON CONCRETE PILE BENT PIERS W/ EXPOSED TIMBER PILES AND PILE BENT ABUTMENTS, ±67'-0" BK. TO BK., AND ±26'-0" O. TO O., NO SKEW (TO BE REMOVED)

SECTION 07-00099-00-BR ENDS STATION 164+00.00

APPROVED Calm W Home MORGAN COUNTY ENGINEER DISTRICT SIX ENGINEER OF LOCAL ROADS & STREETS

LOCATION OF SECTION INDICATED THUS: -

SIGNATURE

DISTRICT SIX ENGINEER OF CONSTRUCTION Released For Bid Based on Limited Review

DEPUTY DIRECTOR OF HIGHWAYS. REGION FOUR ENGINEER

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

UTILITY COMPANIES

FRONTIER COMMUNICATIONS JACKSONVILLE. ILLINOIS

ILLINOIS RURAL ELECTRIC WINCHESTER, ILLINOIS

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

NET LENGTH OF PROJECT = 1,300.00 FEET = 0.246 MILES DESIGN CLASSIFICATION: MAJOR-COLLECTOR (NON-URBAN) DESIGN ADT = 1.075 (2031) DESIGN SPEED = 40 MPH

APPROXIMATE SCALE

LOCATION MAP

STRUCTURE ON CONC. SPILL THRU PILE BENT

ABUTMENTS & CONC. ENCASED PILE BENT PIERS,

163'-9" BK. TO BK. AND 30'-0" O. TO O., O° SKEW

Hutchison Engineering, Inc.

JACKSONVILLE ILLINOIS

CONTRACT NO. 93545

2010

ENGINEERS SEAL