ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUIL' QUANTITIE
AR108084	1/C #4 XLP-USE	L.F.	2,800	QOANTITIE
AR108086	1/C #6 XLP-USE	L.F.	2,520	
AR108108	1/C #8 5 KV UG CABLE	L.F.	1,872	
AR108158	1/C #8 5KV UG CABLE IN UD	L.F.	11,162	
AR108554	2/C #4 600V UG CABLE IN UD	L.F.	302	
AR108654	3/C #4 600V UG CABLE IN UD	L.F.	3,381	
AR108656	3/C #6 600V UG CABLE IN UD	L.F.	2,041	
AR108812	12 PAIR CONTROL CABLE	L.F.	900	
AR109110	ERECT PREFABRICATED VAULT	L.S.	1	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1	
AR109901	REMOVE ELECTRICAL VAULT	L.S.	1	
AR110014	4" DIRECTIONAL BORE	L.F.	517	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	430	
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	682	
AR110610	ELECTRICAL HANDHOLE	EACH	6	
AR110710	ELECTRICAL MANHOLE	EACH	6	
AR125410	MITL-STAKE MOUNTED	EACH	30	
AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	2	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	2	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	4	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	2	
AR125505	MIRL, STAKE MOUNTED	EACH	24	
AR125510	MIRL, BASE MOUNTED	EACH	8	
AR125540	MI THRESHOLD LIGHT STAKE MTD	EACH	16	
	SPLICE CAN	EACH EACH	6	-
AR125565	PLASI	EACH EACH	2	
AR125630				
AR125961	RELOCATE STAKE MOUNTED LIGHT	EACH	2	
AR125989	REFURBISH PLASI	EACH	2	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR151450	CLEARING AND GRUBBING	ACRE	27.3	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	29,797	
AR155540	BY-PRODUCT LIME	TON	1,120	
AR155616	SOIL PROCESSING - 16"	S.Y.	31,115	
AR156510	SILT FENCE	L.F.	2,625	
AR156511	DITCH CHECK	EACH	14	
AR156521	HEADWALL PROTECTION	EACH	6	
AR156530	TEMPORARY SEEDING	ACRE	43.7	
AR156531	EROSION CONTROL BLANKET	S.Y.	12,241	
AR156544	RIPRAP - GRADATION NO. 4	S.Y.	911	
AR162900	REMOVE CLASS E FENCE	L.F.	79	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	10,884	
AR401614	BIT. SURF. CSE METHOD II, SUPERPAVE	TON	2.958	
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	2,272	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	367	
AR403614	BIT. BASE CSE. – METHOD II, SUPERPAVE	TON	4,904	
AR403630	BITUMINOUS BASE TEST SECTION	EACH	1	
AR602510	BITUMINOUS PRIME COAT	GAL.	10,884	
AR602510 AR603510	BITUMINOUS TACK COAT	GAL.	5,609	
AR620520	PAVEMENT MARKING — WATERBORNE	S.F.	20,734	
				-
AR620525	PAVEMENT MARKING - BLACK BORDER 4" PVC STORM SEWER	S.F.	7,688	
AR701004		L.F.	100	-
AR701008	8" PVC STORM SEWER	L.F.	100	-
AR701010	10" PVC STORM SEWER	L.F.	100	-
AR701515	15" RCP, CLASS IV	L.F.	235	
AR701530	30" RCP. CLASS IV	L.F.	188	-
AR701536	36" RCP, CLASS IV	L.F.	186	
AR701542	42" RCP, CLASS IV	L.F.	552	
AR705410	POROUS BACKFILL	C.Y.	370	
AR705526	6" PERFORATED UNDERDRAIN W/ SOCK	L.F.	7,198	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	24	
AR705900	REMOVE UNDERDRAIN	L.F.	1,009	
AR705903	REMOVE UNDERDRAIN INSP. HOLE	EACH	4	
AR752415	PRECAST REINFORCED CONCRETE FES 15"	EACH	4	
AR752430	PRECAST REINFORCED CONCRETE FES 30"	EACH	1	
AR752442	PRECAST REINFORCED CONCRETE FES 42"	EACH	1	
AR752630	CONCRETE HEADWALL 30"	EACH	1	
AR752636	CONCRETE HEADWALL 36"	EACH	2	
AR752642	CONCRETE HEADWALL 30 CONCRETE HEADWALL 42"	EACH	1	
AR800543	FIELD TILE REPAIR	EACH	5	
MN0000043		ACRE		
AR901510	SEEDING		43.7	

SUMMARY OF QUANTITIES ADDITIVE ALTERNATE NO. 1							
	ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES		
	AS101580	REFURBISH 36" BEACON	L.S.	1			
\subset	AS800591	UPGRADE AIRPORT ROTATING BEACON	L.S.	1			

SUMMARY OF QUANTITIES ADDITIVE ALTERNATE NO. 2							
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES			
AT107712	L-807 WIND CONE - 12' LIGHTED	EACH	1				
AT108656	3/C #6 600V UG CABLE IN UD	L.F.	250				

ED017

DATE REVISION

NOIS

EDGAR COUNTY AIRPORT PARIS, ILLINOIS

Honson Proj. No. 10A0053

Filename R—002FLP.DWG

Scale NTO TO SCALE

Date 03/10/11

Copyright Honson Professional Services Inc. 2011
Hanson Professional Services Inc. 1525 South Sixth Street
Springfield, Illinois 62703-2886
www.hanson-inc.com
Offices Nationwide

CONSTRUCT CROSSWIND RUNWAY 18-36

3 of 137 sheets

SUMMARY OF QUANTITIES