


THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

TIE PROPOSED CABLE INTO EXISTING AT THIS STAKE MOUNTED LIGHT. PROTECT EXISTING LIGHT FIXTURES, & COORDINATE WITH TAXIWAY CONSTRUCTION.

EXISTING MITL CABLE TO BE REMOVED TO ACCOMMODATE NEW CONSTRUCTION.

- LEGEND**
- EXISTING IMPROVEMENTS
  - PROPOSED IMPROVEMENTS
  - EXISTING ELECTRICAL CABLES
  - EXISTING ELECTRICAL CABLES (TO BE REMOVED)
  - PROPOSED 1/C #8, FAA L-824 5KV CABLE IN UNIT DUCT
  - EXISTING STAKE MOUNTED RUNWAY LIGHT
  - EXISTING BASE MOUNTED RUNWAY LIGHT
  - EXISTING TAXI GUIDANCE SIGN
  - EXISTING STAKE MOUNTED TAXIWAY LIGHT
  - PROPOSED STAKE MOUNTED TAXIWAY LIGHT
  - PROPOSED RELOCATED STAKE MOUNTED TAXIWAY LIGHT



MAR 14, 2011 9:13 AM HAGL000382 I:\AIRPORTS\LITCHFIELD\10A0094\CADD\AIRPORT\SHEET\R-141ELE.DWG - STA. 82+00 TO STA. 87+00

DATE	REVISION	BY																
<p><b>LITCHFIELD MUNICIPAL AIRPORT</b> <b>LITCHFIELD, ILLINOIS</b></p> <p>IL PROJ.: 3LF-4046 A.I.P. PROJ.: 3-17-0063-B17</p>																		
<p>Hanson Project No. 10A0094D_0800                  File Name: R-141ELE.DWG                  Scale: 1" = 30'                  Date: 02/04/11</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>LAYOUT</td> <td>BAK</td> <td>07/19/10</td> </tr> <tr> <td>DRAWN</td> <td>BAK</td> <td>07/19/10</td> </tr> <tr> <td>REVIEWED</td> <td>KNL/CAH</td> <td>12/22/10</td> </tr> </table>										LAYOUT	BAK	07/19/10	DRAWN	BAK	07/19/10	REVIEWED	KNL/CAH	12/22/10
LAYOUT	BAK	07/19/10																
DRAWN	BAK	07/19/10																
REVIEWED	KNL/CAH	12/22/10																
<p>Hanson Professional Services Inc.                  15601 S. State Street                  Springfield, IL 62703-2886                  Offices Nationwide</p>																		
<p><b>TAXIWAY "C" EXTENSION</b></p> <p>PROPOSED ELECTRICAL PLAN                  STA. 82+00 TO STA. 87+00</p>																		
<p><b>23</b></p> <p>23 of 70 sheets</p>																		