

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS
2	LIST OF HIGHWAY STANDARDS
2	GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5	EXISTING AND PROPOSED TYPICAL CROSS SECTIONS
6-7	SCHEDULE OF QUANTITIES
8-11	PLAN SHEET
12-16	PAVEMENT MARKING PLAN SHEETS
17-19	ADA RAMP DETAIL
20	D5 DISTRICT DETAIL 7200100

LIST OF HIGHWAY STANDARDS

STANDARD NO.	NAME OF STANDARD
000001-08	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND A FOOT
424001-11	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
424026-03	ENTRANCE/ ALLEY PEDESTRIAN CROSSINGS
424031-02	MEDIAN PEDESTRIAN CROSSINGS
442201-03	CLASS C AND D PATCHES
604001-05	FRAME AND GRATE, TYPE 3
606001-08	CONCRETE CURB TYPE B AND COMBINATION CURB AND GUTTER
701006-05	OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5M) TO 24" (600MM) FROM PAVEMENT EDGE
701301-04	LANE CLOSURES, 2L, 2W, SHORT TIME OPERATIONS
701901-08	TRAFFIC CONTROL DEVICES
780001-05	TYPICAL PAVEMENT MARKINGS
886001-01	DETECTOR LOOP INSTALLATIONS
886006-01	TYPICAL LAYOUT FOR DETECTION LOOPS

GENERAL NOTES

G.N.-100A
ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION INCLUDING CADD FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.

G.N.-105.09A
ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988. (NAVD 88)

G.N.-406H

Location	D5 Parking Lot
Mixture Use	Polymer Surface
AC/PG	PG 70-22
Design Air Voids	4.0% @ Ndes=50
Mix Comp(Gradation)	IL 9.5
Friction Aggregate	Mix C
Mixture Weight	112
Quality Management Program	QC/QA
Sublot Size	N.A.
Material Transfer Device (Required ?)	No

G.N.-440B

THE EXISTING TIE BARS BETWEEN THE EXISTING PAVEMENT AND EXISTING MEDIANS, GUTTERS AND/OR COMBINATION CURB AND GUTTERS THAT ARE FOUND SUITABLE FOR REUSE SHALL BE CLEANED, STRAIGHTENED AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY EXISTING TIE BARS THAT ARE FOUND UNSUITABLE TO BE INCORPORATED INTO THE PROPOSED CONSTRUCTION DUE TO EXCESSIVE RUSTING OR DISTRESS SHALL BE REMOVED FLUSH WITH THE FACE OF THE EXISTING CONCRETE AND DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT-OF-WAY IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.

THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE VARIOUS REMOVAL PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

COMMITMENTS

THERE ARE NO COMMITMENTS FOR THIS CONTRACT.

LIST OF DISTRICT DETAILS

DISTRICT DETAIL NUMBER	DESCRIPTION
72000100	DISABLE PARKING

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, LIST OF HIGHWAY STANDARDS
AND GENERAL NOTES**

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARIS IMP 2022-1	EDGAR	20	2
			CONTRACT NO. 70F44	
ILLINOIS FED. AID PROJECT				

1 REV 4/8/22 REV. 2/15/22

SUMMARY OF QUANTITIES

LOCATION OF WORK: PARIS HEADQUARTERS COMPLEX
 EAST PARKING LOT
 URBAN
 COUNTY: EDGAR
 FUNDING BREAKOUT: 100% STATE
 CONSTRUCTION TYPE CODE: 0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
40600290	BITUMINOUS MATERIAL (TACK COAT)	POUND	6,420.0
40604160	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	<del style="text-align: right;">1,610.0
40604100	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "C", N50	TON	1,610.0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	300.0
* 42400800	DETECTABLE WARNINGS	SQ FT	90.0
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2.0"	SQ YD	14,270.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	14.0
44000600	SIDEWALK REMOVAL	SQ FT	300.0
44200050	WELDED WIRE REINFORCEMENT	SQ YD	750.0
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	750.0
44213204	TIE BARS 3/4"	EACH	35.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	1.0
60250600	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	9.0
60300350	MANHOLE FRAMES TO BE ADJUSTED	EACH	5.0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	14.0
* DENOTES SPECIALTY ITEM			



MODEL: \\MODELNAME\$
 FILE: \\NAME\$.pnt
 PLOT DATE: 02/04/22

USER NAME = meglisk	DESIGNED -	REVISED -
PLOT SCALE = 40:0' = 1" / in.	DRAWN -	REVISED -
PLOT DATE = 02/04/22	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARIS IMP 2022-1	EDGAR	20	3
			CONTRACT NO. 70F44	
ILLINOIS FED. AID PROJECT				