



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 13, 2022

SUBJECT: FAI Route 80 (I-80)
Project NHPP-NLNX(934)
Section (06-1HB-2 & 06-2HB)BR
Bureau County
Contract No. 66K73
Item No. 107, April 29, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Revised page 4 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
STATUS OF UTILITIES TO BE ADJUSTED	2
ROAD CLOSURE REQUIREMENTS	4
FENCE REMOVAL	4
BORROW AND FURNISHED EXCAVATION.....	5
SHOULDER STABILIZATION AT GUARDRAIL.....	5
REMOVAL OF EXISTING STRUCTURES NO. 1.....	6
REMOVAL OF EXISTING STRUCTURES NO. 2.....	6
VEHICLE PARKING.....	6
KEEPING ROADS OPEN TO TRAFFIC.....	7
TRAFFIC CONTROL AND PROTECTION, (SPECIAL).....	7
CHANGEABLE MESSAGE SIGN	7
DETOUR SIGNING.....	8
TRAFFIC CONTROL SURVEILLANCE	8
PLASTIC DRUMS.....	8
REMOVE ATTENUATOR BASE.....	8
REMOVE IMPACT ATTENUATORS, NO SALVAGE.....	9
TEMPORARY INFORMATION SIGNING.....	9
PAINT PAVEMENT MARKING – TWO APPLICATIONS	10
LINEAR DELINEATOR PANELS, 4 INCH.....	10
LINEAR DELINEATION PANELS (TEMPORARY BARRIER WALL)	12
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES.....	13
SLIPFORM PARAPET	14
BRIDGE DECK CONSTRUCTION.....	18
PREFORMED PAVEMENT JOINT SEAL	19
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	25
BLENDED FINELY DIVIDED MINERALS (BDE).....	26
COMPENSABLE DELAY COSTS (BDE)	26
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	30
FUEL COST ADJUSTMENT (BDE)	38

Revised April 13, 2022

ROAD CLOSURE REQUIREMENTS

(Effective January 1, 2016)

The Contractor will be allowed to close 645E Road (SN 006-0117), 470E Road (SN 006-0121), and I-80 as shown on the plans for the replacement of the structure. Road closure requirements include:

1. Closure of SN 006-0117 and SN 006-0121 at the same time will not be allowed. SN 006-0117 shall be closed and reconstructed first followed by SN 006-0121. 470E cannot be closed until 645E is open. All lanes and shoulders on I-80 shall be open to traffic between December 1, and the following March 1.
2. The closure of I-80 will only be allowed for operations for the removal of the existing beams, the placement of new beams over the interstate, and any other demolition work as approved by the Engineer. Closure of I-80 will only be allowed between 8:00 pm and 6:00 am. Liquidated damages for failure to open the road to two-way traffic by 6:00 am will be deducted according to Article 108.09.
3. The Contractor shall notify the Engineer at least 21 days in advance of the road closures. The Engineer must then notify the permit office in Springfield by email at DOT.Roadinfo@Illinois.gov.
4. The Contractor shall provide the traffic control devices used to close the roads as shown on the plan details and applicable standards.
5. The closures shall begin as approved by the Engineer and only after the Engineer has notified the local emergency services, school system, postal service, etc. of the closure. This notification must come at least one week in advance of the closures.
6. After each structure has been replaced, the pavement and shoulders repaired, and guardrail installed, the associated road closure shall be removed and the road shall be opened to two-lane, two-way traffic.

FENCE REMOVAL

Description. This item shall consist of furnishing all labor, equipment, and materials necessary for the removal and disposal of the existing woven wire fence at the locations shown in the plans or otherwise directed by the Engineer. All work shall be done in accordance with the applicable portions of Section 501 of the Standard Specifications.

Construction Requirements. No removal work shall be completed without the approval of the Engineer. All elements, hardware and appurtenances of the existing fence including, but not limited to, wire mesh, posts, connecting elements, bolts, baseplates, shim plates, elastomeric pads, and anchor bolts shall be removed and included within this Item.

Revised April 13, 2022