



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 12, 2022

SUBJECT: FAS Routes 323/FAP 71 (IL 54)  
Project STP-Z1KQ(351)  
Section (112&112Z)&(38-5HB-4)RS-3,SW  
Iroquois County  
Contract No. 66K77  
Item No. 201, April 29, 2022 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 44 to the Special Provisions.
4. Revised sheets 3 and 11 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

FUEL COST ADJUSTMENT (BDE) .....30  
HOT-MIX ASPHALT – START OF PRODUCTION (BDE).....32  
MATERIAL TRANSFER DEVICE (BDE) .....32  
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE) .....34  
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE).....35  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....35  
SURFACE TESTING OF PAVEMENTS – IRI (BDE).....36  
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....41  
WEEKLY DBE TRUCKING REPORTS (BDE).....41  
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....42  
WORKING DAYS (BDE).....43  
PREPARATION AND RESTORATION OF SIDEWALK WORK AREAS .....44

## **PREPARATION AND RESTORATION OF SIDEWALK WORK AREAS**

At any locations where the existing sidewalk elevations require modification to meet ADA compliance, the work shall include leveling and shaping of the existing ground/subbase to provide for the required ADA compliant slopes as shown in the plan details, including any required furnished excavation, earth excavation under the proposed sidewalk necessary to complete the work and restore any disturbed areas.

The Contractor shall restore the sidewalk work area as specified in Article 104.06 of the Standard Specifications. All damage to mowed lawns shall be replaced with an approved sod, and all damage to unmowed fields shall be seeded. This work will not be paid for separately, but shall be included in the cost of the associated sidewalk pay items. Restoration items include, but are not limited to, furnished excavation, earth excavation, seeding, sodding, fertilizer nutrients, and erosion control blanket.

Earth Excavation required for the removal of non-special waste disposal will be measured and paid separately.

The 4-Inch Aggregate Base Course, Type B (CA 6 material) required for the sidewalks will be measured and paid separately.

Added April 12, 2022