

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

F	LE NAME =	USER NAME = aqueelff	DESIGNED -	REVISED - R. MIRS 09-15-97			ARTERIAL ROAD	F.A.U.	SECTION	COUNTY	TOTAL S	HEET
c	\pw_work\PWIDOT\AQUEELFF\dØ169846\Dis	tStd.dgn	DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS	INFORMATION SIGN		0381	90-RS-4	WILL	15	15
		PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION			1000	TC-22	CONTRACT		69
L		PLOT DATE = 12/29/2009	DATE ~	REVISED - C. JUCIUS 01-31-07	\$	SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD D	DIST. NO. 1 ILLINOIS FED. AI			