








\* DIMENSIONS OF THE CURB & GUTTER AT SECTION A-A ARE SHOWN ON STATE STANDARD GOGODI. FOR DETAILS OF OUTLET FOR CONCRETE CURB & GUTTER, TYPE B-6.24 (B-15.60) SEE STATE STANDARD GOGODG.














## GENERAL NOTES

GUTTER OUTLET SHALL BE TIED TO THE PAVEMENT IN ACCORDANCE WITH DETAILS FOR LONGITUDINAL CONSTRUCTION JOINT SHOWN ON STANDARD 420001.

TIE BARS SHALL BE NO. 20 (NO.6) AT 24" (600) CENTERS UNLESS OTHERWISE SHOWN.

IF THE AVERAGE CRADE OF PAVEMENT FOR THE DISTANCE FROM SECTION A-A TO D-D EXCEEDS 2%, THIS DISTANCE SHALL BE INCREASED 6' (1.8 m) FOR EACH 1% INCREASE IN GRADE.

## QUANTITIES

FOR SECTION A-A TO E-E AND CURTAIN WALL=
1.25 CU. YDS. (0.96 m<sup>3</sup>) CLASS SI CONCRETE (OUTLET) FOR 9" (225) PAV'T.
1.27 CU. YDS. (0.96 m<sup>3</sup>) CLASS SI CONCRETE (OUTLET) FOR 10" (250) PAV'T.
FOR SECTION F-F=
0.045 CU. YDS. (0.03 m<sup>3</sup>) CLASS SI CONCRETE PER ft. (m).

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

## **OUTLET FOR CONCRETE CURB AND GUTTER**

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -			DISTRICT STANDARDS		F.A.P.	SECTION	COUNTY	TOTAL SHEET
\$FILEL\$		DRAWN -	REVISED -	STATE OF ILLINOIS	IL ROUTE 59 OVER SQUAW CREEK			104	W-EXT-I	LAKE	21 14
1	PLOT SCALE = *SCALE*	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION					BD-03	CONTRACT	F NO. 60J52
	PLOT DATE = \$DATE\$	DATE -	REVISED ~		SCALE: NONE	SHEET NO. OF SHEETS STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			