SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	23	23					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17					
40600300	AGGREGATE (PRIME COAT)	TON	82	82					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	31	31					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	841	841					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	81	81					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1712	1712					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	20376	20376					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	245	245					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	164	164					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	46	46					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2650	2650					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19890	19890					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	450	450					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	633	633					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	38	38					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	884	884					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19890	19890					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	450	450					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	633	633					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	38	38					

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	175	175					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	145	145					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
*	SPECIALY ITEMS								

FILE NAME = c:\pw_work\pwidot\whitefar\d0175521\D126210-sht-plan.dgn	USER NAME = whitefar	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/2/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1521	W-RS-5	KANE	16	3
		CONTRACT NO. 60J72		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT