INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	EXISTING AND PROPOSED TYPICAL SECTIONS
5-8	ROADWAY AND PAVEMENT MARKING PLANS
9	DRIVEWAY DETAILS - DISTANCE BETWEEN R.O.W. AND FACE OF CURB & EDGE OF SHOULDER >= 15'
10	BUTT JOINT AND HMA TAPER
11	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
12	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
13	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
14	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
15	ARTERIAL INFORMATION SIGNING

GENERAL NOTES:

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

THE CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.

HOT-MIX ASPHALT TAPERS SHALL BE INSTALLED AT THE ENDS OF PULVERIZATION (WHERE PULVERIZED PAVEMENT MEETS EXISTING PAVEMENT) IN ACCORDANCE WITH THE "BUTT JOINT AND HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS UNLESS OTHERWISE SPECIFIED.

THE RESIDENT ENGINEER SHALL CONTACT MS. CORA MATHIS, AREA TRAFFIC FIELD ENGINEER, AT (815) 485-6475 A MINIMUM OF 2 WEEKS PRIOR TO PLACEMENT OF FINAL PAVEMENT MARKINGS.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC, THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1½INCHES WHERE THE SPEED LIMIT IS 45 MPH OR LESS, AND 1 INCH WHERE THE SPEED LIMIT IS OVER 45 MPH. WITH WRITTEN APPROVAL FROM THE RESIDENT ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM OF 1:3 (V:H).

THE RESIDENT ENGINEER SHALL VERIFY LOCATIONS OF ALL EXISTING PAVEMENT MARKINGS PRIOR TO MILLING OR RESURFACING.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE INSTALLATION OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

STATE STANDARDS:

SHEET NO.	DESCRIPTION:
000001- <i>05</i>	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
406201 <i>-01</i>	MAILBOX TURNOUTS
630001- <i>00</i>	GUARDRAIL STEEL PLATE BEAM
630301- <i>05</i>	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, SHOULDER WIDENING FOR
635006 <i>- 03</i>	REFLECTOR AND TERMINAL MARKER PLACEMENT
701301 - <i>03</i>	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311 - <i>03</i>	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701501 - <i>05</i>	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701901-01	TRAFFIC CONTROL DEVICES

FILE NAME =	USER NAME = rosierejm	DESIGNED ~	REVISED -		I EF MEAT F	PRODUCE OF TOAR (CAMANAMOM ROAD TO BUILDING ROAD		D TO BAHDDIN DOAD	F.A.I.	SECTION	COUNTY	TOTAL	SHEET
c:\pw_work\PWIDOT\ROSIEREJM\d0175433\D	0126410-sht-plan.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS		I-55 WEST FRONTAGE ROAD (CAVANAUGH ROAD TO MURPHY ROAD)			D) RTE.	99-24C-1-PC-2	WTI	SHEETS	S NO.
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	INDEX	DEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES			1 33 1	33-2AC-1-N3-2	CONTRACT	T NO 6	0.174
	PLOT DATE = 1/30/2010	DATE -	REVISED -		SCALE:	SHEET NO. OF	SHEETS STA.	TO STA.	1	ILLINOIS FED. AI	D PROJEC	7 110. 0	5014