

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| FILE NAME = | USER NAME = gorengouteb | DESIGNED - | REVISED - | R. MIRS 09-15-9 | | | ARTERIAL ROAD | | | | | F.A.U. RTE. | SECTION | COUNTY | TOTAL | SHEET NO. |
|--|-----------------------------|------------|-----------|-------------------|------|------------------------------|---------------|---------------|-----------|--------|---------|-------------------------------------|------------|-------------|-------|--------------|
| c:\pw_work\pwidot\gorengautab\d0177815\0 | ıstStd.dgn | DRAWN - | REVISED - | R. MIRS 12-11-9 | | STATE OF ILLINOIS | | | | | | 2682 | 0102. 1 RS | соок | 19 | 18 |
| | PLOT SCALE = 50.0000 '/ IN. | CHECKED - | REVISED - | T. RAMMACHER 02-0 | 2-99 | DEPARTMENT OF TRANSPORTATION | | | | | | TC-22 | CONTRAC | CT NO. | 60J79 | |
| | PLOT DATE = 2/2/2010 | DATE - | REVISED - | C. JUCIUS 01-31 | 07 | | SCALE: NONE | SHEET NO. 1 0 | F 1 SHEET | S STA. | TO STA. | FED. ROAD DIST. NO. 1 ILLINOIS FED. | | AID PROJECT | | |