

SIDE ROAD & ENTRANCES									
LOCATION	STATION	RT/LT	INCIDENTAL	BIT	HMA	TEMP.	FURN.	AGG	
			HMA SURF	MATLS PR CT	SURF REM. BUTT JT.	RAMP	EX*	PR CT	
			TON	GAL	SQ YD	SQ YD	CU YD	TON	
CE	646+28	LT	17.5	11.1	138.8			0.3	
CE	647+28	LT	17.5	11.1	138.8			0.3	
CE	647+98	RT	21.0	13.4	167.0			0.3	
TR 69-A	650+48	LT	61.6	39.1	488.6	22.2	2.0	1.0	
RAMP A	652+80	R	80.4	51.0	638.0	7.1	2.0	1.3	
RAMP B	653+42	LT	87.8	55.6	695.0	7.1	2.0	1.4	
RAMP C	665+73	RT	87.6	55.6	695.0	7.1	2.0	1.4	
RAMP D	666+25	LT	80.4	51.0	638.0	7.1	2.0	1.3	
900 E	674+50	RT/LT	62.5	39.7	496.0	23.1	4.0	1.0	
CE	678+02	RT	4.0	2.5	31.7			0.1	
CE	680+63	RT	2.7	1.7	21.5			0.0	
MBT	687+30	RT	0.9	0.6	7.2			0.0	
PE	687+61	LT	3.5	2.2	27.5			0.1	
CE	688+90	LT	6.1	3.9	48.4			0.1	
CE	690+90	LT	5.5	3.5	43.5			0.1	
MICHIGAN ST	695+10	RT	19.3	12.2	153.1	11.6	2.0	0.3	
PE	695+60	LT	4.5	2.9	35.9			0.1	
CE	696+00	LT	5.0	3.2	39.5			0.1	
CE	2+30	RT	NO WORK - BEHIND CCC & G						
CE	2+90	RT	4.2	2.6	33.0			0.1	
CE	3+80	RT	5.0	3.2	39.5			0.1	
2ND ST	6+00	RT	16.0	10.2	127.1	10.7	2.0	0.3	
PE/MBT	7+50	RT	3.5	2.2	27.5			0.1	
CE	8+52	RT	6.5	4.1	51.4			0.1	
PE	9+42	RT	4.2	2.7	33.6			0.1	
PE	11+00	LT	3.7	2.4	29.4			0.1	
3RD ST	11+02	RT	3.7	2.4	29.7	10.7	2.0	0.1	
PE/MBT	12+61	RT	3.7	2.4	29.4			0.1	
PE	15+25	RT	3.3	2.1	26.4			0.1	
4TH ST	15+78	RT	17.6	11.2	139.7	10.7	2.0	0.3	
PE	18+42	RT	3.6	2.3	28.7			0.1	
5TH ST	21+06	RT	15.3	9.7	121.6	10.7	2.0	0.2	
1000 E	30+56	RT/LT	24.5	15.5	194.1	14.6	4.0	0.4	
PE	54+60	RT	4.2	2.7	33.5			0.1	
MBT	54+60	LT	4.2	2.7	33.5			0.1	
PE	57+40	RT	2.8	1.8	22.2			0.0	
PE	59+60	LT	3.2	2.0	25.1			0.1	
MBT	60+50	LT	3.0	1.9	24.2			0.0	
1100E	83+89	RT/LT	22.2	14.1	176.5	14.6	4.0	0.4	
PE	105+54	RT	3.1	2.0	24.8			0.0	
MBT	105+54	LT	3.0	1.9	23.9			0.0	
PE	115+57	RT	2.8	1.8	22.5			0.0	
MBT	115+57	LT	5.1	3.3	40.7			0.1	
1200 E	136+89	RT/LT	24.1	15.3	191.6	14.6	4.0	0.4	
CE/MBT	155+17	RT	5.2	3.3	41.3			0.1	
PE	156+75	LT	3.4	2.2	27.0			0.1	
1300 E	190+54	RT/LT	24.7	15.7	196.4	14.6	4.0	0.4	
			817.3	503.8	6297.8	186.5	40.0	13.0	

PERMANENT SURVEY MARKERS, TYPE 1	
LOCATION	EACH
30+27	1
83+60	1
136+80	1
TOTAL	3

SEE COMMITMENT FILE FOR TIE POINTS

*PLACE FURNISHED EX AROUND SIDERAOD RADII. THIS AREA TO BE SEEDED, FERTILIZED AND MULCHED- NOT PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION

FILE NAME =	USER NAME = sellnr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca\pw\work\p\dot\sellnr\d0119889\d36693	-sht-details.dgn	DRAWN -	REVISED -			681	(117,118)RS-3	IROQUOIS	11	6	
	PLOT SCALE = 58.1686' / IN.	CHECKED -	REVISED -			CONTRACT NO. 66931					
	PLOT DATE = Jan 29, 2010 - 11:38:11 AM	DATE -	REVISED -			[ILLINOIS] FED. AID PROJECT					