

PAVEMENT MARKING SCHEDULE

STA. TO STA.	THERMOPLASTIC PAVEMENT MARKING						PAINT PVT MK			TEMPORARY PAVEMENT MARKING						SHORT TERM	WORK ZONE PAVT	RAISED REFLECT.	RAISED REFLECT.	
	4" WHT	4" YELL	8" WHT	12" WHT	12" YELL	24" WHT	4" WHT	4" YELL	6" YELL	4" WHT	4" YELL	8" WHT	6" YELL	12" WHT	12" YELL	24" WHT	PAV'T MARK	MARK REM.	PVT MK REM	PVT MK
	FT	FT	FT	FT	FT	FT				FT	FT	FT	FT	FT	FT	FT	FT	SQ FT	EACH	EACH
254+74 TO 267+00	2454	3520		256	710	114				2454	3520			256	710	71	2000	130	44	44
267+00 TO 749+00							96400	8554	12050	96400	8554		12050				19280	1590	603	603
NO PASSING ZONES*								8553			8553									
IL 40																				
NORTH LEG	1080	1760	200		355	13				1080	1760	200					162	1	22	22
SOUTH LEG	1080	1760	200		355	13				1080	1760	200							22	22
IL 172																				
NORTH LEG	250	80	100	64		12				250	80	100		64		12	100	10		
SUBTOTALS	4864	7120		320	1420	152	96400	17107	12050	101264	24227		12050	320	1420	109	21542	1731	691	691
TOTALS	11984		500	1740		152	113507		12050	125491		500	12050	1740		152	21542	1731	691	691

NOTE: THE FOLLOWING NO PASSING ZONES SHOULD BE FIELD VERIFIED BY THE ENGINEER PRIOR TO RESURFACING (IN MILEAGE FROM HENRY COUNTY LINE, INCREASING AS TRAVELING EAST)

EB STA. 5.6 TO 5.9	WB STA. 5.7 TO 6.1
EB STA. 6.8 TO 6.82	WB STA. 6.8 TO 7.1
EB STA. 7.1 TO 7.3	WB STA. 7.3 TO 7.5

GUARDRAIL

STRUCTURE LOCATION	TBT TY 1 SPL (TANGENT)	GUARDRAIL REMOVAL	SPBGR, TYPE A	TERMINAL MARKER - DA	FURNISHED EXCAVATION*
	EA	FOOT	FOOT	EA	CU YD
SN 006-1001 (MM 2.9)	4	200		4	20
SN 006-0096 (MM 4.7)*	4	250	50	4	20
SN 006-0098 (MM 8.2)	4	200		4	20
TOTAL	12	650	50	12	60

FURNISHED EX. TO BE PLACED AT END SECTIONS ACCORDING TO STD. 630301
MILE MARKER (MM) 0.00 IS THE HENRY COUNTY LINE
* CLOSE GUARDRAIL GAP BETWEEN END SCTIONS ON SOUTH SIDE OF ROADWAY

*THIS AREA TO BE SEEDED, FERTILIZED AND MULCHED- NOT PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION