CONTRACT NO. 70022

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	12

* (58,74-66)&(74-67&68)RS-1

SUMMARY OF QUANTITES

	LOCATION OF WORK:			MACON COUNTY RURAL FAI-72 STA. 910+00.00 TO STA. 932+59.22	PIATT COUNTY RURAL FAI-72 STA. 932+59.22 TO STA. 1308+92.00 & STA. 1216+11.00 TO 1377+89.00	PIATT COUNTY URBAN FAI-72 STA. 1308+92.00 TO 1216+11.00	PIATT COUNTY RURAL STRUCTURE S.N. 074-0055	PIATT COUNTY RURAL STRUCTURE S.N. 074-0058	PIATT COUNTY RURAL STRUCTURE S.N. 074-0062	PIATT COUNTY RURAL STRUCTURE S.N. 074-0063 S.N. 074-0064	PIATT COUNTY URBAN STRUCTURE S.N. 074-0067
	CONSTRUCTION TYPE CODE:			I000	I000	I000	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A
CODE NO	ITEM	UNIT	TOTAL QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY	100% STATE QUANTITY
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	56.0						56.0		
X0324103	SILICONE JOINT SEALER, 4"	FOOT	54.0								54.0
X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	21.0		17.5	3.5					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	190.0				166.0			24.0	
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	12.0	2.0	5.0	5.0					
X0703200	CONCRETE ISLAND (SPECIAL)	SQ FT	717.1		717.1						
X0323583	SPEED INDICATOR SIGN	CAL DA	160.0	80.0	80.0						
X5080600	MECHANICAL SPLICE RS	EACH	122.0				122.0				
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	14.0	14.0						
44003100	MEDIAN REMOVAL	SQ FT	3,033.0		3,033.0						
60623711	CONCRETE MEDIAN	SQ FT	3,033.0		3,033.0						
X0326874	SILICONE JOINT SEALER, 3"	FOOT	63.0					63.0			
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	2,269.0				1,352.0			917.0	
Z0000600	ADJUST FRAMES FOR INLETS	EACH	4.0		2.0	2.0					
Z0004810	HOT-MIX ASPHALT FOR PATCHING	TON	281.0		108.0	173.0					
Z0006204	BRIDGE DECK HYDRO - SCARIFICATION 1/2"	SQ YD	2,269.0				1,352.0			917.0	
Z0012500	CONCRETE CURB REPAIR	FOOT	5.0		5.0						
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	5.0				5.0				
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	15.0				15.0				
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	95.0						95.0		

* SPECIALTY ITEMS

(CONT'D NEXT SHEET)

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I. ROUTE 72
SECTION (58,74-66)&(74-67&68)RS-1
PIATT COUNTY
Sheet 7 of 8

SCALE: NONE
DRAWN BY:
DATE: 01/30/10
CHECKED BY: R.T.B.

PLOT DATE = 2/8/2010
FILE NAME = c:\pw_work\PWIDOT\CEARLCOX\D0578622\dist578_sht_sum.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = cearlcox