

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	34

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

48203100 HOT MIX ASPHALT SHOULDERS

		STATION	IQ	STATION		LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	SHOULDER THICKNESS (INCHES)	48203100 HMA SHLD (TON)	40600100 BIT MATLS PR CT (GAL)	40600300 AGG PR CT (TONS)
I-72 MEDIAN SHOULDERS												
	I-72 EB	LT	910+00.00	LT	932+59.22	2259.2	6.0	1506.1	1.75	147.6	150.6	3.0
	I-72 EB	LT	932+59.22	LT	965+00.00	3240.8	6.0	2160.5	1.75	211.7	216.1	4.3
	I-72 EB	LT	965+00.00	LT	1210+00.00	24500.0	6.0	16333.3	1.75	1600.7	1633.3	32.7
	I-72 EB	LT	1210+00.00	LT	1278+85.96	6886.0	6.0	4590.6	1.75	449.9	459.1	9.2
	I-72 EB	LT	1278+85.96	LT	1279+32.96	47.0	6.0	31.3	1.50	2.6	3.1	0.1
	I-72 EB	LT	1280+39.13	LT	1280+86.13	47.0	6.0	31.3	1.50	2.6	3.1	0.1
	I-72 EB	LT	1280+86.13	LT	1308+92.00	2805.9	6.0	1870.6	1.75	183.3	187.1	3.7
	I-72 EB	LT	1308+92.00	LT	1421+31.00	11239.0	6.0	7492.7	1.75	734.3	749.3	15.0
	I-72 EB	LT	1421+31.00	LT	1421+86.52	55.5	6.0	37.0	1.50	3.1	3.7	0.1
	I-72 EB	LT	1428+63.44	LT	1429+18.90	55.5	6.0	37.0	1.50	3.1	3.7	0.1
	I-72 EB	LT	1429+18.90	LT	1436+37.00	718.1	6.0	478.7	1.75	46.9	47.9	1.0
	I-72 EB	LT	1436+37.00	LT	1436+95.20	58.2	6.0	38.8	1.50	3.3	3.9	0.1
	I-72 EB	LT	1439+18.28	LT	1439+76.00	57.7	6.0	38.5	1.50	3.2	3.8	0.1
	I-72 EB	LT	1439+76.00	LT	1464+20.00	2444.0	6.0	1629.3	1.75	159.7	162.9	3.3
	I-72 EB	LT	1464+20.00	LT	1492+62.04	2842.0	4.0	1263.1	1.75	123.8	126.3	2.5
	I-72 EB	LT	1492+62.04	LT	1499+41.06	679.0	4.0	301.8	4.75	80.3	30.2	0.6
	I-72 EB	LT	1162+63.35	LT	1216+11.00	5347.6	4.0	2376.7	4.75	632.2	237.7	4.8
	I-72 EB	LT	1216+11.00	LT	1265+71.09	4960.1	4.0	2204.5	4.75	586.4	220.4	4.4
	I-72 EB	LT	1265+30.54	LT	1299+70.10	3439.6	4.0	1528.7	4.75	406.6	152.9	3.1
	I-72 EB	LT	1299+70.10	LT	1300+54.10	84.0	4.0	37.3	2.50	5.2	3.7	0.1
	I-72 EB	LT	1302+62.80	LT	1303+16.80	54.0	4.0	24.0	2.50	3.4	2.4	0.0
	I-72 EB	LT	1303+16.80	LT	1377+89.00	7472.2	4.0	3321.0	4.75	883.4	332.1	6.6
SUB-TOTAL =										6273.3	4733.3	94.7

I-72 MEDIAN SHOULDERS (CONTINUED)

	I-72 WB	RT	910+00.00	RT	932+59.22	2259.2	6.0	1506.1	1.75	147.6	150.6	3.0
	I-72 WB	RT	932+59.22	RT	965+00.00	3240.8	6.0	2160.5	1.75	211.7	216.1	4.3
	I-72 WB	RT	965+00.00	RT	1210+00.00	24500.0	6.0	16333.3	1.75	1600.7	1633.3	32.7
	I-72 WB	RT	1210+00.00	RT	1279+13.88	6913.9	6.0	4609.3	1.75	451.7	460.9	9.2
	I-72 WB	RT	1279+13.88	RT	1279+80.88	47.0	6.0	31.3	1.50	2.6	3.1	0.1
	I-72 WB	RT	1280+67.05	RT	1281+14.05	47.0	6.0	31.3	1.50	2.6	3.1	0.1
	I-72 WB	RT	1281+14.05	RT	1308+92.00	2778.0	6.0	1852.0	1.75	181.5	185.2	3.7
	I-72 WB	RT	1308+92.00	RT	1422+25.00	11333.0	6.0	7555.3	1.75	740.4	755.5	15.1
	I-72 WB	RT	1422+25.00	RT	1422+80.50	55.5	6.0	37.0	1.50	3.1	3.7	0.1
	I-72 WB	RT	1429+57.42	RT	1430+12.90	55.5	6.0	37.0	1.50	3.1	3.7	0.1
	I-72 WB	RT	1430+12.90	RT	1437+65.00	752.1	6.0	501.4	1.75	49.1	50.1	1.0
	I-72 WB	RT	1437+65.00	RT	1438+22.94	57.9	6.0	38.6	1.50	3.2	3.9	0.1
	I-72 WB	RT	1440+46.02	RT	1441+04.00	58.0	6.0	38.7	1.50	3.2	3.9	0.1
	I-72 WB	RT	1441+04.00	RT	1464+20.00	2316.0	6.0	1544.0	1.75	151.3	154.4	3.1
	I-72 WB	RT	1464+20.00	RT	1488+42.09	2422.1	4.0	1076.5	1.75	105.5	107.6	2.2
	I-72 WB	RT	1488+42.09	RT	1499+41.06	1099.0	4.0	488.4	4.75	129.9	48.8	1.0
	I-72 WB	RT	1162+63.35	RT	1216+11.00	5347.6	4.0	2376.7	4.75	632.2	237.7	4.8
	I-72 WB	RT	1216+11.00	RT	1265+71.09	4960.1	4.0	2204.5	4.75	586.4	220.4	4.4
	I-72 WB	RT	1265+30.54	RT	1299+66.62	3436.1	4.0	1527.1	4.75	406.2	152.7	3.1
	I-72 WB	RT	1299+66.62	RT	1300+45.62	79.0	4.0	35.1	2.50	4.9	3.5	0.1
	I-72 WB	RT	1302+54.29	RT	1303+20.29	66.0	4.0	29.3	2.50	4.1	2.9	0.1
	I-72 WB	RT	1303+20.29	RT	1377+89.00	7468.7	4.0	3319.4	4.75	883.0	331.9	6.6
SUB-TOTAL =										6304.3	4733.3	94.7

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\pwwork\pwwork\d01019678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = ceer-lockjd

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY

Sheet 1 of 6 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.