

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	38

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

48203100 HOT MIX ASPHALT SHOULDERS (CONTD)

		STATION	TO	STATION		LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	SHOULDER THICKNESS (INCHES)	48203100 HMA SHLD (TON)	40600100 BIT MATLS PR CT (GAL)	40600300 AGG PR CT (TONS)
I-72 INTERCHANGE NO. 166 AT IL 105 RAMP SHOULDERS												
RAMP A	RT	100+00.00	RT	100+35.00	TAPER	35.00	VAR	35.0	1.75	3.4	3.5	0.1
RAMP A	RT	100+35.00	RT	106+50.00		615.00	8.0	546.7	1.75	53.6	54.7	1.1
RAMP A	RT	106+50.00	RT	119+77.77		1327.77	8.0	1180.2	1.75	115.7	118.0	2.4
RAMP A	RT	119+77.77	RT	121+15.01		225.16	8.0	249.5	1.50	21.0	25.0	0.5
RAMP A	LT	105+55.00	LT	106+00.00	GORE	45.00	VAR	85.0	5.00	23.8	8.5	0.2
RAMP A	LT	106+00.00	LT	119+77.77		1377.77	5.0	765.4	1.75	75.0	76.5	1.5
RAMP A	LT	119+77.77	LT	121+15.01		153.30	5.0	93.0	1.50	7.8	9.3	0.2
RAMP B	RT	200+23.00	RT	201+26.47		170.46	8.0	151.5	1.50	12.7	15.2	0.3
RAMP B	RT	201+26.47	RT	210+76.00		949.53	8.0	844.0	1.75	82.7	84.4	1.7
RAMP B	RT	210+76.00	RT	221+16.00		1040.00	8.0	924.4	1.75	90.6	92.4	1.8
RAMP B	RT	221+16.00	RT	222+66.00	TAPER	150.00	VAR	150.0	1.75	14.7	15.0	0.3
RAMP B	LT	200+23.00	LT	201+26.47		109.20	VAR	64.0	1.50	5.4	6.4	0.1
RAMP B	LT	201+26.47	LT	210+76.00		949.53	4.5	474.8	1.50	39.9	47.5	0.9
RAMP B	LT	210+76.00	LT	212+96.00	GORE	220.00	VAR	281.1	5.00	78.7	28.1	0.6
RAMP C	RT	300+00.00	RT	301+60.00	TAPER	160.00	VAR	160.0	1.75	15.7	16.0	0.3
RAMP C	RT	301+60.00	RT	306+00.00		440.00	8.0	391.1	1.75	38.3	39.1	0.8
RAMP C	RT	306+00.00	RT	315+13.65	Sta Eqn	913.65	8.0	812.1	1.75	79.6	81.2	1.6
RAMP C	RT	510+77.64	RT	501+53.96		923.68	8.0	821.0	1.50	69.0	82.1	1.6
RAMP C	RT	501+53.96	RT	500+23.23		227.00	8.0	235.9	1.50	19.8	23.6	0.5
RAMP C	LT	305+15.00	LT	306+00.00	GORE	85.00	VAR	151.1	5.00	42.3	15.1	0.3
RAMP C	LT	306+00.00	LT	315+13.65		913.65	4.0	406.1	1.75	39.8	40.6	0.8
RAMP D	RT	500+23.23	RT	500+86.40		59.70	8.0	53.1	1.50	4.5	5.3	0.1
RAMP D	RT	500+86.40	RT	510+77.64	Sta Eqn	991.24	8.0	881.1	1.50	74.0	88.1	1.8
RAMP D	RT	411+07.83	RT	420+72.00		964.17	8.0	857.0	1.75	84.0	85.7	1.7
RAMP D	RT	420+72.00	RT	432+57.01		1185.01	8.0	1053.3	1.75	103.2	105.3	2.1
RAMP D	LT	411+07.83	LT	420+72.00		964.17	4.0	428.5	1.75	42.0	42.9	0.9
SUB-TOTAL =										1237.1	1209.5	24.2

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\pwwork\cear1lock\j\d0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cear1lockj

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
 Sheet 5 of 6 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.