

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	40

\*(58,74-66)&(74-67&68)RS-1

## SCHEDULES

**48203029 HOT MIX ASPHALT SHOULDERS, 8 INCH**

		STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	HMA SHLD 8 THICKNESS (INCHES)	HMA SHLD 8 (TON)	48203029 AREA (SQ YD)
<b>I-72 INTERCHANGE NO. 156 AT IL48 RAMP SHOULDERS</b>									
RAMP A	RT	100+23.81	RT	100+68.81	93.3	2.0	8.00	9.3	20.7
RAMP A	RT	100+68.81	RT	101+19.88	51.7	2.0	8.00	5.1	11.5
RAMP A	RT	101+19.88	RT	113+05.00	1185.1	2.0	8.00	118.0	263.4
RAMP A	RT	113+05.00	RT	122+85.00	980.0	2.0	8.00	97.6	217.8
RAMP A	RT	122+85.00	RT	124+75.90	190.9	2.0	8.00	19.0	42.4
RAMP B	RT	200+00.00	RT	201+30.00	130.0	2.0	8.00	12.9	28.9
RAMP B	RT	201+30.00	RT	206+45.00	515.0	2.0	8.00	51.3	114.4
RAMP B	RT	206+45.00	RT	217+90.25	1145.3	2.0	8.00	114.0	254.5
RAMP B	RT	217+90.25	RT	218+68.02	82.2	2.0	8.00	8.2	18.3
RAMP B	RT	218+68.02	RT	219+13.02	127.2	2.0	8.00	12.7	28.3
RAMP C	RT	300+23.81	RT	300+68.81	93.2	2.0	8.00	9.3	20.7
RAMP C	RT	300+68.81	RT	301+19.88	51.7	2.0	8.00	5.1	11.5
RAMP C	RT	301+19.88	RT	313+30.00	1210.1	2.0	8.00	120.5	268.9
RAMP C	RT	313+30.00	RT	323+05.00	975.0	2.0	8.00	97.1	216.7
RAMP C	RT	323+05.00	RT	324+75.90	170.9	2.0	8.00	17.0	38.0
RAMP D	RT	400+00.00	RT	400+60.00	60.0	2.0	8.00	6.0	13.3
RAMP D	RT	400+60.00	RT	406+55.00	595.0	2.0	8.00	59.2	132.2
RAMP D	RT	406+55.00	RT	417+90.25	1135.3	2.0	8.00	113.0	252.3
RAMP D	RT	417+90.25	RT	418+68.02	82.3	2.0	8.00	8.2	18.3
RAMP D	RT	418+68.02	RT	419+13.02	127.2	2.0	8.00	12.7	28.3
<b>SUB-TOTAL =</b>								<b>896.1</b>	<b>2000.3</b>

PLOT DATE = 2/8/2010  
 FILE NAME = c:\pwwork\pwwork\cear.lock\j\d0109678\TEXT2899.DGN  
 PLOT SCALE = 105.8824 / IN.  
 USER NAME = cear.lockj

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72  
SECTION (58,74-66)&(74-67&68)RS-1  
PIATT COUNTY  
*Sheet 1 of 4 Sheets*

SCALE: NONE      DRAWN BY: CADD  
DATE: 12/15/09      CHECKED BY: R.T.B.