

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	53

\*(58,74-66)&(74-67&68)RS-1

# SCHEDULES

**70300100 SHORT-TERM PAVEMENT MARKING**

I-72 MAINLINE CENTERLINE, LT EOP, RT EOP

		STATION	IQ	STATION	MILLING FOOT	BINDER FOOT	SURFACE FOOT	70300100 TOTAL FOOT	70301000 WK ZN PVT MK REM SQ FT
Mcn RL	I-72 EB	910+00.00		932+59.22	677.8	677.8	677.8	2033.3	223.7
Piat RL	I-72 EB	932+59.22		965+00.00	972.2	972.2	972.2	2916.7	320.8
	I-72 EB	965+00.00		1210+00.00	7350.0	7350.0	7350.0	22050.0	2425.5
	I-72 EB	1210+00.00		1279+32.96	2079.9	2079.9	2079.9	6239.7	686.4
0063	I-72 EB	1279+32.96		1280+39.13	31.9	31.9	31.9	95.6	10.5
	I-72 EB	1280+39.13		1308+92.00	855.9	855.9	855.9	2567.6	282.4
Piat Urb	I-72 EB	1308+92.00		1421+86.52	3388.4	3388.4	3388.4	10165.1	1118.2
0067	I-72 EB	1421+86.52		1428+63.44	203.1	203.1	203.1	609.2	67.0
	I-72 EB	1428+63.44		1436+95.20	249.5	249.5	249.5	748.6	82.3
0069	I-72 EB	1436+95.20		1439+18.28	66.9	66.9	66.9	200.8	22.1
	I-72 EB	1439+18.28		1464+20.00	750.5	750.5	750.5	2251.5	247.7
	I-72 EB	1464+20.00		1499+41.06	1056.3	1056.3	1056.3	3169.0	348.6
Sta Eqn	I-72 EB	1162+63.35		1216+11.00	1604.3	1604.3	1604.3	4812.9	529.4
Piat RL	I-72 EB	1216+11.00		1265+71.09	1488.0	1488.0	1488.0	4464.1	491.0
Sta Eqn	I-72 EB	1265+30.54		1300+54.10	1057.1	1057.1	1057.1	3171.2	348.8
0001	I-72 EB	1300+54.10		1302+62.80	62.6	62.6	62.6	187.8	20.7
	I-72 EB	1302+62.80		1377+89.00	2257.9	2257.9	2257.9	6773.6	745.1
SUB-TOTAL =								72456.5	7970.2

**70300100 SHORT-TERM PAVEMENT MARKING (CONT'D)**

I-72 MAINLINE CENTERLINE, LT EOP, RT EOP

		STATION	IQ	STATION	MILLING FOOT	BINDER FOOT	SURFACE FOOT	70300100 TOTAL FOOT	70301000.0 WK ZN PVT MK REM SQ FT
Mcn RL	I-72 WB	910+00.00		932+59.22	677.8	677.8	677.8	2033.3	223.7
Piat RL	I-72 WB	932+59.22		965+00.00	972.2	972.2	972.2	2916.7	320.8
	I-72 WB	965+00.00		1210+00.00	7350.0	7350.0	7350.0	22050.0	2425.5
	I-72 WB	1210+00.00		1279+60.88	2088.3	2088.3	2088.3	6264.8	689.1
0064	I-72 WB	1279+60.88		1280+67.05	31.9	31.9	31.9	95.6	10.5
	I-72 WB	1280+67.05		1308+92.00	847.5	847.5	847.5	2542.5	279.7
Piat Urb	I-72 WB	1308+92.00		1422+80.50	3416.6	3416.6	3416.6	10249.7	1127.5
0068	I-72 WB	1422+80.50		1429+57.42	203.1	203.1	203.1	609.2	67.0
	I-72 WB	1429+57.42		1438+22.94	259.7	259.7	259.7	779.0	85.7
0070	I-72 WB	1438+22.94		1440+46.02	66.9	66.9	66.9	200.8	22.1
	I-72 WB	1440+46.02		1464+20.00	712.2	712.2	712.2	2136.6	235.0
	I-72 WB	1464+20.00		1499+41.06	1056.3	1056.3	1056.3	3169.0	348.6
Sta Eqn	I-72 WB	1162+63.35		1216+11.00	1604.3	1604.3	1604.3	4812.9	529.4
Piat RL	I-72 WB	1216+11.00		1265+71.09	1488.0	1488.0	1488.0	4464.1	491.0
Sta Eqn	I-72 WB	1265+30.54		1300+45.62	1054.5	1054.5	1054.5	3163.6	348.0
0002	I-72 WB	1300+45.62		1302+54.29	62.6	62.6	62.6	187.8	20.7
	I-72 WB	1302+54.29		1377+89.00	2260.4	2260.4	2260.4	6781.2	745.9
SUB-TOTAL =								72456.5	7970.2

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72  
SECTION (58,74-66)&(74-67&68)RS-1  
PIATT COUNTY  
Sheet 1 of 2 Sheets

SCALE: NONE DRAWN BY: CADD  
DATE: 12/15/09 CHECKED BY: R.T.B.

PLOT DATE = 2/8/2010  
FILE NAME = c:\pwwork\cear\lock\j\d0109678\TEXT2899.DGN  
PLOT SCALE = 105.8824 / IN.  
USER NAME = cear\lockj