

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	57

\*(58,74-66)&(74-67&68)RS-1

## SCHEDULES

**78000200 THERMOPLASTIC PAVEMENT MARKING LINE - 4" (WHITE)**

		STATION	IQ	STATION	LENGTH (FOOT)
<b>I-72 INTERCHANGE NO. 156 AT IL48 RAMPS</b>					
RAMP A	RT	100+23.81	RT	101+19.88	144.9
RAMP A	RT	101+19.88	RT	124+75.90	2356.0
RAMP B	RT	200+00.00	RT	217+90.25	1790.3
RAMP B	RT	217+90.25	RT	219+13.02	209.4
RAMP C	RT	300+23.81	RT	301+19.88	144.9
RAMP C	RT	301+19.88	RT	324+75.90	2356.0
RAMP D	RT	400+00.00	RT	417+90.25	1790.3
RAMP D	RT	417+90.25	RT	419+13.02	209.4
<b>SUB-TOTAL =</b>					<b>9001.1</b>

**78000200 THERMOPLASTIC PAVEMENT MARKING LINE - 4" (WHITE)**

		STATION	IQ	STATION	LENGTH (FOOT)
<b>I-72 INTERCHANGE NO. 164 AT FAP 135 (BRIDGE ST) RAMPS</b>					
RAMP A	RT	100+23.81	RT	101+19.88	144.9
RAMP A	RT	101+19.88	RT	124+11.52	2291.6
RAMP B	RT	200+00.00	RT	218+65.64	1865.6
RAMP B	RT	218+65.64	RT	219+88.42	209.5
RAMP C	RT	300+23.81	RT	301+19.88	144.9
RAMP C	RT	301+19.88	RT	324+11.52	2291.6
RAMP D	RT	400+00.00	RT	418+50.28	1850.3
RAMP D	RT	418+50.28	RT	419+88.40	235.6
<b>SUB-TOTAL =</b>					<b>9034.1</b>

**78000200 THERMOPLASTIC PAVEMENT MARKING LINE - 4" (WHITE)**

		STATION	IQ	STATION	LENGTH (FOOT)
<b>I-72 INTERCHANGE NO. 164 AT IL 105 RAMPS</b>					
RAMP A	RT	100+00.00	RT	119+77.77	1977.77
RAMP A	RT	119+77.77	RT	121+15.01	225.16
RAMP B	RT	200+23.00	RT	201+26.47	170.50
RAMP B	RT	201+26.47	RT	222+65.86	2139.39
RAMP C	RT	300+00.00	RT	315+13.65	1513.65
RAMP C	RT	510+77.64	RT	501+53.96	923.68
RAMP C	RT	501+53.96	RT	500+23.23	227.00
RAMP D	RT	500+23.23	RT	500+86.40	59.70
RAMP D	RT	500+86.40	RT	510+77.64	991.24
RAMP D	RT	411+07.83	RT	432+57.01	2149.18
<b>SUB-TOTAL =</b>					<b>10377.3</b>

**78000200 THERMOPLASTIC PAVEMENT MARKING LINE - 4" (WHITE)**

		STATION	IQ	STATION	LENGTH (FOOT)
<b>I-72 INTERCHANGE NO. 169 AT FAS 1532 ( OLD 47 ) RAMPS</b>					
RAMP A	RT	100+11.17	RT	100+70.12	84.86
RAMP A	RT	100+70.12	RT	119+94.40	1924.28
RAMP B	RT	200+00.00	RT	215+80.31	1580.31
RAMP B	RT	215+80.31	RT	216+58.86	128.25
RAMP C	RT	300+11.19	RT	300+67.45	80.50
RAMP C	RT	300+67.45	RT	319+23.55	1856.10
RAMP D	RT	400+00.00	RT	418+96.99	1896.99
RAMP D	RT	418+96.99	RT	419+72.07	119.86
<b>SUB-TOTAL =</b>					<b>7671.2</b>

**TOTAL = 182337.6**

**USE = 182340.0**

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72  
SECTION (58,74-66)&(74-67&68)RS-1  
PIATT COUNTY  
Sheet 2 of 4 Sheets

SCALE: NONE DRAWN BY: CADD  
DATE: 12/15/09 CHECKED BY: R.T.B.