

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	64

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

RAISED REFLECTIVE PAVEMENT MARKERS (CONT'D)

		STATION	TO	STATION	(FOOT)	78300200 RAISED REFL PVT MK REM EACH	78100100 CRYSTAL RAISED REFL PVT MKR EACH	78100100 YELLOW RAISED REFL PVT MKR EACH
INTERCHANGE NO.166 AT IL 105								
I-72 EB	RT	1465+12.00		RT	1469+22.00	410.0	10	0
RAMP C	LT	302+40.00		LT	306+62.00	422.0	11	0
RAMP C	LT	306+62.00		LT	315+13.65	851.7	21	21
RAMP C	RT	505+29.00		RT	510+78.00	549.0	14	14
RAMP C	RT	300+00.00		RT	306+62.00	662.0	33	0
I-72 WB	LT	1481+18.00		LT	1486+13.00	495.0	12	0
RAMP A	LT	102+05.00		LT	106+62.00	457.0	11	0
RAMP A	LT	106+62.00		LT	113+92.00	730.0	18	18
RAMP A	RT	100+00.00		RT	106+62.00	662.0	33	0
SUB-TOTAL =						164	111	53

RAISED REFLECTIVE PAVEMENT MARKERS (CONT'D)

		STATION	TO	STATION	(FOOT)	78300200 RAISED REFL PVT MK REM EACH	78100100 CRYSTAL RAISED REFL PVT MKR EACH	78100100 YELLOW RAISED REFL PVT MKR EACH
INTERCHANGE NO.169 AT OLD 47								
I-72 EB	RT	1274+50.00		RT	1277+86.00	336.0	8	0
RAMP D	LT	403+65.00		LT	405+81.00	216.0	5	0
RAMP D	LT	405+81.00		LT	411+08.00	527.0	13	13
RAMP D	RT	400+00.00		RT	405+81.00	581.0	29	0
I-72 WB	LT	1281+67.00		LT	1284+35.00	268.0	7	0
RAMP B	LT	204+32.00		LT	205+81.00	149.0	4	0
RAMP B	LT	205+81.00		LT	213+50.00	769.0	19	19
RAMP B	RT	200+00.00		RT	206+50.00	650.0	33	0
SUB-TOTAL =						118	86	32
TOTAL =						2561	2417	144

USE TOTAL RRPV REMOVAL = 2565 EACH

USE TOTAL RRPV = 2565

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\cear\lock\j\d0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cear\lockj

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
SECTION (58,74-66)&(74-67&68)RS-1
PIATT COUNTY
Sheet 3 of 3 Sheets

SCALE: NONE DRAWN BY: CADD
DATE: 12/15/09 CHECKED BY: R.T.B.